



DEVELOPMENT APPLICATION

An architectural rendering of a modern, multi-story data center building. The building features a prominent dark grey facade with the 'NEXTDC' logo in large, orange and white letters. The logo includes a stylized graphic of server racks. The building has a flat roof and is surrounded by a parking lot with several cars. In the background, there are green fields and a blue sky with scattered clouds. The rendering is presented in a wide-angle perspective.4/10/2025 11:42:00 AM



02/02/2025	ARC	DC PACKAGE - AMENDMENTS	HSA	ALL	HSA
04/02/2025	ARC	DC PACKAGE	HSA	ALL	HSA
21/02/2025	ARC	DC REVIEW PACKAGE	HSA	ALL	HSA
08/03/2025	ARC	DC REVIEW PACKAGE	HSA	ALL	HSA
20/03/2025	ARC	DC REVIEW PACKAGE	HSA	ALL	HSA
11/03/2025	ARC	DEVELOPMENT APPLICATION PACKAGE	HSA	ALL	HSA
08/03/2025	ARC	FOR INFORMATION	HSA	ALL	HSA
08/03/2025	ARC	FOR INFORMATION	HSA	ALL	HSA
18/03/25	ARC	FOR INFORMATION	HSA	ALL	HSA
DATE	WHO	REVISION/REMARKS	ISSUED	DATE	BY

NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CONFIRM ALL MEASUREMENTS ON SITE
4. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
5. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS
Architect HAMES SHARLEY
Services AURECON
Structural PRITCHARD FRANCIS

PRINCIPAL CONTRACTOR

CLIENT




(Contractor / Consultant / Document Author)

Hames Sharley
hamessharley.com.au +61 8 9381 0200

Document Author Project Number

Key Plan



Site	Stage	NEXTDC Project Number
D2	0101	D1.0004

Project Address
2 RYKO CT (LOT 9704) &
6 RYKO CT (LOT 9703),
DARWIN CITY, 8000,
NORTHERN TERRITORY

Project Name

NEXTDC D2 STAGE 1

Drawing Title

LOCATION PLAN

Drawing Status
SPATIAL COORDINATION
FOR INFORMATION


Drawn	Check
HSA	09/02/2025
Checked	Draw
AD	09/02/2025
Approved	Date
JLS	09/02/2025

Scale Sheet File Name

1:200 A1 02-ARC-HSA-PCA-A-001-BUILDING

Drawn By Rev

D2-ARC-HSA-PCA-A-0100-0010 SPC-6



02/02/2023	SPC	DA PACKAGE - AMENDMENTS	150A	ALL	150A
24/07/2023	SPC	DA PACKAGE	150A	ALL	150A
21/01/2023	SPC	DA REVIEW PACKAGE	150A	ALL	150A
08/01/2023	SPC	DA REVIEW PACKAGE	150A	ALL	150A
28/12/2023	SPC	DA REVIEW PACKAGE	150A	ALL	150A
11/12/2023	SPC	DEVELOPMENT APPLICATION PACKAGE	150A	ALL	150A
08/12/2023	SPC	FOR INFORMATION	150A	ALL	150A
08/12/2023	SPC	FOR INFORMATION	150A	ALL	150A
18/12/23	SPC	FOR INFORMATION	150A	ALL	150A
DATE	REV	REVISIONS/REMARKS	ISSUED	DATE	BY

- NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
 2. DO NOT SCALE FROM DRAWINGS
 3. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
 4. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS

Architect HAMES SHARLEY

Services AURECON

Structural PRITCHARD FRANCIS

PRINCIPAL CONTRACTOR

CLIENT




(Contractor / Consultant / Document Author)

Hames Sharley

Document Author Project Number

Key Plan



Site	Stage	NEXTDC Project Number
D2	0101	D1.0004

Project Address

2 RYKO CT (LOT 9704) & 6 RYKO CT (LOT 9703), DARWIN CITY, 8000, NORTHERN TERRITORY

Project Name

NEXTDC D2 STAGE 1

Drawing Title

PROPOSED SITE PLAN

Drawing Status

SPATIAL COORDINATION FOR INFORMATION

DRAWN	DATE
15/02/2023	15/02/2023
CHECKED	DATE
15/02/2023	15/02/2023
APPROVED	DATE
15/02/2023	15/02/2023

Scale	Sheet	File Name
1:200	A1	02-ARC-HSA-PCA-A-001-BUILDING

Drawn by	Rev
D2-ARC-HSA-ORG-A-0100-0020	SPC-6

4/10/2023 11:46:12 AM



02/02/2025	SPC	DA PACKAGE AMENDMENTS	HSA	ALL	HSA
24/07/2025	SPC	DA PACKAGE	HSA	ALL	HSA
21/01/2025	SPC	DA REVIEW PACKAGE	HSA	ALL	HSA
08/01/2025	SPC	DA REVIEW PACKAGE	HSA	ALL	HSA
28/12/2024	SPC	DA REVIEW PACKAGE	HSA	ALL	HSA
11/02/2024	SPC	DEVELOPMENT APPLICATION PACKAGE	HSA	ALL	HSA
08/01/2024	0	FOR INFORMATION	HSA	ALL	HSA
08/01/2024	0	FOR INFORMATION	HSA	ALL	HSA
18/10/24	0	FOR INFORMATION	HSA	ALL	HSA
DATE		REVISION/REVISION	02/02/2025	1.0	1.0

- NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
 2. DO NOT SCALE FROM DRAWINGS
 3. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
 4. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS

Architect HAMES SHARLEY

Services AURECON

Structural PRITCHARD FRANCIS

PRINCIPAL CONTRACTOR

CLIENT




[Contractor / Consultant / Document Author]

Hames Sharley

Document Author Project Number

Key Plan



Site	Stage	NEXTDC Project Number
D2	0101	D1.0004

Project Address

2 RYKO CT (LOT 9704) &
6 RYKO CT (LOT 9703),
DARWIN CITY, 8000,
NORTHERN TERRITORY

Project Name

NEXTDC D2 STAGE 1

Drawing Title

PERSPECTIVE 2

Drawing Status

SPATIAL COORDINATION
FOR INFORMATION

DRAWN	DATE
HSA	09/02/2025
CHECKED	DATE
AD	09/02/2025
APPROVED	DATE
JLS	09/02/2025

Scale	Sheet	File Name
	A1	02-ARC-HSA-PCA-A-0101-BUILDING

Drawn by	Rev
D2-ARC-HSA-PCA-A-0101-0031	SPC-6



02/02/2025	SPC	DA PACKAGE - AMENDMENTS	150A	ALL	150A
24/07/2025	SPC	DA PACKAGE	150A	ALL	150A
21/01/2025	SPC	DA REVIEW PACKAGE	150A	ALL	150A
08/01/2025	SPC	DA REVIEW PACKAGE	150A	ALL	150A
28/12/2024	SPC	DA REVIEW PACKAGE	150A	ALL	150A
11/12/2024	SPC	DEVELOPMENT APPLICATION PACKAGE	150A	ALL	150A
08/12/2024	D	FOR INFORMATION	150A	ALL	150A
08/12/2024	D	FOR INFORMATION	150A	ALL	150A
18/12/24	D	FOR INFORMATION	150A	ALL	150A
DATE	REV	DESCRIPTION / REVISION	ISSUED	DATE	BY

NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
4. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS
Architect HAMES SHARLEY
Services AURECON
Structural PRITCHARD FRANCIS

PRINCIPAL CONTRACTOR


CLIENT

NEXTDC
GPO Box 3219
Brisbane QLD 4001
T: +61 7 3177 4177

[Contractor / Consultant / Document Author]
Hames Sharley
hamessharley.com.au +61 8 9381 0200

Document Author Project Number

Key Plan



Site	Stage	NEXTDC Project Number
D2	0101	D1.0004

Project Address
2 RYKO CT (LOT 9704) &
6 RYKO CT (LOT 9703),
DARWIN CITY, 8000,
NORTHERN TERRITORY

Project Name
NEXTDC D2 STAGE 1

Drawing Title
PERSPECTIVE 3

Drawing Status
SPATIAL COORDINATION
FOR INFORMATION

DRAWN	DATE	BY
HSA	03/02/2025	
CHECKED	DATE	BY
AD	03/02/2025	
APPROVED	DATE	BY
JLS	03/02/2025	

Scale	Sheet	File Name
	A1	02-ARC-HSA-PDA-A-0101-BUILDING

Drawn by	Rev
D2-ARC-HSA-ORG-A-0100-0032	SPC-6



02/02/2025	SPC	SPC PACKAGE - AMENDMENTS	HSA	ALL	HSA
24/07/2024	SPC	SPC PACKAGE	HSA	ALL	HSA
21/01/2025	SPC	SPC REVISION PACKAGE	HSA	ALL	HSA
08/01/2025	SPC	SPC REVISION PACKAGE	HSA	ALL	HSA
28/12/2024	SPC	SPC REVISION PACKAGE	HSA	ALL	HSA
11/02/2025	SPC	SPC DEVELOPMENT APPLICATION PACKAGE	HSA	ALL	HSA
08/02/2025	SPC	SPC INFORMATION	HSA	ALL	HSA
08/02/2025	SPC	SPC INFORMATION	HSA	ALL	HSA
08/02/2025	SPC	SPC INFORMATION	HSA	ALL	HSA
DATE	REV	DESCRIPTION / REVISION	BY	CHKD	APPD

- NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
 2. DO NOT SCALE FROM DRAWINGS
 3. CONFIRM ALL MEASUREMENTS ON SITE
 4. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
 5. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS

Architect HAMES SHARLEY

Services AURECON

Structural PRITCHARD FRANCIS

PRINCIPAL CONTRACTOR

CLIENT




NEXTDC
GPO Box 3219
Brisbane QLD 4001
T: +61 7 3177 4777

[Contractor / Consultant / Document Author]

Hames Sharley

Document Author Project Number

Key Plan



Site	Stage	NEXTDC Project Number
D2	0101	D1.0004

Project Address
2 RYKO CT (LOT 9704) &
6 RYKO CT (LOT 9703),
DARWIN CITY, 8000,
NORTHERN TERRITORY

Project Name

NEXTDC D2 STAGE 1

Drawing Title

PERSPECTIVE 5

Drawing Status
SPATIAL COORDINATION
FOR INFORMATION

DRAWN	DATE
HSA	03/02/2025
CHECKED	DATE
AD	03/02/2025
APPROVED	DATE
JLS	03/02/2025

Scale	Sheet	File Name
	A1	02-ARC-HSA-PDR-A-0100-BUILDING

Drawn by	Rev
D2-ARC-HSA-DRG-A-0100-0034	SPC-6

NAME	Area
LOWER GROUND	
CIRCULATION	29 m ²
FIRE TANK B	17 m ²
FUEL TANK A	79 m ²
FUEL TANK B	79 m ²
PARKING	707 m ²
POT. WATER	31 m ²
PWC HV A	26 m ²
PWC HV B	26 m ²
WASTE ROOM	5 m ²
WATER TANK A	12 m ²
WATER TANK B	12 m ²
WATER TANK C	12 m ²
WATER TANK D	12 m ²
	1081 m ²
LOADING DOCK	
BATT A	9 m ²
BATT B	9 m ²
BKE PARKING	35 m ²
CIRCULATION	16 m ²
FIRE BOOSTER	3 m ²
FIRE PUMP ROOM	43 m ²
LIFT CORR.	9 m ²
HV A	27 m ²
HV B	27 m ²
LIFT	15 m ²
LIFT	14 m ²
LIFT	2 m ²
LOADING	36 m ²
NOC STORAGE	48 m ²
PUMP	9 m ²
PUMP	9 m ²
RISERS	23 m ²
STAGING	21 m ²
STAGING	21 m ²
STAIR 1	19 m ²
STAIR 2	17 m ²
STREET AIRLOCK	17 m ²
TELCO ROOM	3 m ²
UNPACK	29 m ²
	498 m ²
GROUND FLOOR	
BREAKOUT / TOWN HALL	102 m ²
CIRCULATION	210 m ²
CIRCULATION	27 m ²
CLEANERS	11 m ²
COMMS	8 m ²
CONCERGE	11 m ²
CONTRACTOR BREAKOUT	26 m ²
ENTRY AIRLOCK	23 m ²
EDT	14 m ²
ESHALE	14 m ²
FIRE TANK A	17 m ²
FIRE TANK B	17 m ²
INTERCONNECT	25 m ²
INTERCONNECT	25 m ²
LIFT	2 m ²
LIFT	15 m ²
LIFT	14 m ²
LOBBY / ENTRY	109 m ²
MALE	14 m ²
MCX MEETING	23 m ²
MCX OFFICE	401 m ²
MCX STORAGE	102 m ²
MCX STORAGE	109 m ²
NOC STORAGE	98 m ²
NEXTDC BREAKOUT	36 m ²
NEXTDC BREAKOUT (OUTDOOR)	38 m ²
NEXTDC MEETING	20 m ²
NEXTDC OFFICE	108 m ²
PNBAL / MESSAGE	14 m ²
PLANT CAPUS	67 m ²
QU. RM.	6 m ²
QU. RM.	6 m ²
SEC. TRAP	10 m ²
SEC. TRAP	5 m ²
SEC. WC	6 m ²
SECURITY OFFICE	35 m ²

NAME	Area
SHR	4 m ²
SHR	4 m ²
STAIR 1	19 m ²
STAIR 2	17 m ²
UAT	19 m ²
UAT	6 m ²
UNIVERSAL	19 m ²
UTILITY	9 m ²
WATER TANK A	12 m ²
WATER TANK B	12 m ²
WATER TANK C	12 m ²
WATER TANK D	12 m ²
	1900 m ²
LEVEL 1	
AMB. WC	3 m ²
BREAKOUT	19 m ²
CIRCULATION	47 m ²
COMMS	8 m ²
DATA HALL	1931 m ²
LIFT	15 m ²
LIFT	14 m ²
LIFT LOBBY CORRIDOR	91 m ²
RISER	4 m ²
SERVICES CORRIDOR	192 m ²
SERVICES CORRIDOR	173 m ²
STAIR 1	19 m ²
STAIR 2	17 m ²
	1692 m ²
LEVEL 2	
AMB. WC	3 m ²
BREAKOUT	19 m ²
CIRCULATION	47 m ²
COMMS	8 m ²
DATA HALL	1931 m ²
LIFT	15 m ²
LIFT LOBBY CORRIDOR	91 m ²
RISER	4 m ²
SERVICES CORRIDOR	192 m ²
SERVICES CORRIDOR	173 m ²
STAIR 1	19 m ²
STAIR 2	17 m ²
	1692 m ²
LEVEL 3	
AMB. WC	3 m ²
BREAKOUT	19 m ²
CIRCULATION	47 m ²
COMMS	8 m ²
DATA HALL	1931 m ²
LIFT	15 m ²
LIFT	14 m ²
LIFT LOBBY CORRIDOR	91 m ²
RISER	4 m ²
SERVICES CORRIDOR	192 m ²
SERVICES CORRIDOR	173 m ²
STAIR 1	19 m ²
STAIR 2	17 m ²
	1692 m ²
LEVEL 4	
BATTERY ROOM	19 m ²



NAME	Area
BATTERY ROOM	19 m ²
BATTERY ROOM	19 m ²
BATTERY ROOM	19 m ²
BATTERY ROOM	19 m ²
BATTERY ROOM	19 m ²
CIRCULATION	552 m ²
CIRCULATION	37 m ²
COMMS	9 m ²
GAS BOTTLE STORE A	53 m ²
GAS BOTTLE STORE B	51 m ²
HX / PUMPS	31 m ²
HX / PUMPS	31 m ²
HX / PUMPS	31 m ²
HX / PUMPS	31 m ²
HX / PUMPS	31 m ²
LIFT	15 m ²
LIFT	14 m ²
LIFT LOBBY	16 m ²
NDC STORAGE	19 m ²
NDC STORAGE	69 m ²
RISER	2 m ²
RISER	4 m ²
STAIR 1	19 m ²
STAIR 2	17 m ²
SWITCHROOM	72 m ²
SWITCHROOM	72 m ²
SWITCHROOM	72 m ²
SWITCHROOM	72 m ²
SWITCHROOM	72 m ²
SWITCHROOM	1611 m ²
LEVEL 5	
ANT A	9 m ²
ANT B	9 m ²
CHEM STORE	12 m ²
CIRCULATION	25 m ²
CO	2 m ²
CO	2 m ²
FIRE RUMP ROOM	51 m ²
GENERATOR ROOM	37 m ²
GENERATOR ROOM	37 m ²
GENERATOR ROOM	37 m ²
GENERATOR ROOM	37 m ²
GENERATOR ROOM	37 m ²
LIFT	37 m ²
LIFT	15 m ²
LIFT LOBBY	16 m ²
PLANT OAPUS	46 m ²
ROOF SERVICES	1202 m ²
STAIR 1	19 m ²
STAIR 2	17 m ²
	1667 m ²

Name	Area
LOWER GROUND	
CAR PARK	719 m ²
LOADING	158 m ²
	877 m ²
GROUND FLOOR	
MCX OFFICE	413 m ²
MCX STORE	105 m ²
MCX STORE	112 m ²
NDC OFFICE	200 m ²
NDC STORE	103 m ²
OFFICE	27 m ²
	960 m ²
LEVEL 1	
DATA HALL	1103 m ²
	1103 m ²
LEVEL 2	
DATA HALL	1103 m ²
	1103 m ²
LEVEL 3	
DATA HALL	1103 m ²
	1103 m ²
LEVEL 4	
PLANT	1421 m ²
	1421 m ²
LEVEL 5	
PLANT	1493 m ²
	1493 m ²
Grand total	8062 m ²

Name	Area
LEVEL 1	
DATA HALL	1103 m ²
	1103 m ²
LEVEL 2	
DATA HALL	1103 m ²
	1103 m ²
LEVEL 3	
DATA HALL	1103 m ²
	1103 m ²
Grand total	3310 m ²

Name	Area
LOWER GROUND	
CAR PARK	719 m ²
LOADING	158 m ²
	877 m ²
GROUND FLOOR	
WIX OFFICE	413 m ²
OFFICE	27 m ²
	440 m ²
LEVEL 4	
PLANT	1421 m ²
	1421 m ²
LEVEL 5	
PLANT	1693 m ²
	1693 m ²
Grand total	4433 m ²

Name	Area
LEVEL 4	
COMMS	12 m ²
CORE EAST	105 m ²
CORE WEST	93 m ²
GAS BOTTLE STORAGE A	57 m ²
GAS BOTTLE STORAGE B	55 m ²
PLANT	1421 m ²
	1744 m ²
LEVEL 5	
COMMS	69 m ²
CORE EAST	60 m ²
CORE WEST	84 m ²
FIRE PLANT ROOM	65 m ²
PLANT	1493 m ²
	1732 m ²
Grand total	3476 m ²



NOTE:

1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CONFIRM ALL MEASUREMENTS ON SITE
4. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
5. ENSURE COORDINATION WITH OTHER TRADES ON SITE

CLIENT	
--------	--



[Contractor / Consultant / Document Author]

hamessharley.com.au +61 8 9381 0200

Key Plan



Project Address
2 RYKO CT (LOT 9704) &
6 RYKO CT (LOT 9703),
DARWIN CITY, 8000,
NORTHERN TERRITORY





Project Name
NEXTRDC D2 STAGE 1

NEXT DC DZ STAGE 1
Drawing Title

AREA SCHEDULE

Drawing Status
SPATIAL COORDINATION
FOR INFORMATION

DRAWN HSA		Date 03/02/2025
CHECKED AD		Date 03/02/2025
APPROVED JLS		Date 03/02/2025
Scale 1 : 500	Sheet A1	File Name 02-ARC-HSA-R24-A-0201-BUILDING
Dwg no: D2-ARC-HSA-DRG-A-0100-0100		Rev SPC-6

[illegible]

NOTE:

1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CONFIRM ALL MEASUREMENTS ON SITE
4. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
5. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS

Architect JAMES SHARLEY

Services AURECON

RICHARD FRANCIS

PRINCIPAL CONTRACTOR

CLIENT



NEXT DC

NEXTDC
GPO Box 3219
Brisbane QLD 4001
Tel: 07 3238 3232, 07 3238 3233

[Contractor / Consultant / Document Author]

James
SHARLEY

Document Author Project Number

Key Plans



Site	Stage	NEXTDC Project Number
D2	0101	D1.0004

Project Address
2 RYKO CT (LOT 9704) &
6 RYKO CT (LOT 9703),
DARWIN CITY, 8000,
NORTHERN TERRITORY

Project Name	
--------------	--

NEXTDC D2 STAGE 1

Drawing Title

AXONOMETRICS





Drawing Status

SPATIAL COORDINATION
FOR INFORMATION


Drawn	Date
HSA	03/02/2025
Checked	Date

AD	03/02/2025
JLS	03/02/2025

Scale	Sheet	File Name
	A1	D2-APIC-HISA-R24-A-0201-BUILD



23/02/2020	SPC 2A PACKAGE AMENDMENTS	15A	ALL
24/02/2020	SPC 2A PACKAGE	15A	ALL
21/03/2020	SPC 2A REVISION PONDGE	15A	ALL
21/03/2020	SPC 2A REVISION PONDGE	15A	ALL
22/03/2020	SPC 2A REVISION PONDGE	15A	ALL
15/02/2020	FOR INFORMATION	15A	ALL
15/02/2020	FOR INFORMATION	15A	ALL
15/02/2020	FOR INFORMATION	15A	ALL
15/02/2020	FOR INFORMATION	15A	ALL
15/02/2020	FOR INFORMATION	15A	ALL
DATE	NO	REVISION HISTORY	Drawn
NOTE: 1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION 2. 50' HORIZONTAL SCALE FROM DRAWINGS 3. CONTROL ALL MEASUREMENTS ON SITE 4. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES 5. ENSURE COORDINATION WITH OTHER TRADES ON SITE			
PRINCIPAL CONSULTANTS			
Architect	HAMES SHARLEY		
Structural	AURECON		
Services	PRITCHARD FRANCIS		
PRINCIPAL CONTRACTOR			
CLIENT			
 NEXTDC GPO Box 3219 Wellington, QLD 4001 T: +61 7 3137 4777 [Contractor / Consultant / Document Author]  hamesharley.com.au +61 8 9381 0200 Document Author Project Number			
Key Plan			
			
Site	Stage	NEXTDC Project Number	
D2	0101	D1.0004	
Project Address			
2 RYKO CT (LOT 9704) & 6 RYKO CT (LOT 9703), DARWIN CITY, 8000, NORTHERRN TERRITORY			
Project Name			
NEXTDC D2 STAGE 1			
Drawing Title			
SHADOW DIAGRAMS			
Drawing Status			
SPATIAL COORDINATION FOR INFORMATION			
DRAWN	Date		15/02/2025
DESIGNED	Date		03/02/2025
APPROVED	Date		03/02/2025
Scale	Sheet	File Name	
1 : 700	A1	D2-ARC-HSA-DRG-A-0100-0300	
Drawn by	Project Number		Rev
D2-ARC-HSA-DRG-A-0100-0300	0101		001




NO.	DESCRIPTION	DATE	BY	CHKD	APPD
0001	SPC-CA PACKAGE: AMENDMENTS	15/04/2025	AL	AL	AL
0002	SPC-CA PACKAGE	15/04/2025	AL	AL	AL
0003	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0004	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0005	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0006	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0007	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0008	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0009	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0010	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0011	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0012	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0013	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0014	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0015	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0016	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0017	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0018	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0019	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0020	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0021	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0022	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0023	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0024	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0025	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0026	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0027	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0028	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0029	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0030	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0031	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0032	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0033	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0034	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0035	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0036	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0037	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0038	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0039	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0040	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0041	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0042	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0043	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0044	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0045	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0046	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0047	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0048	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0049	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0050	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0051	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0052	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0053	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0054	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0055	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0056	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0057	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0058	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0059	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0060	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0061	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0062	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0063	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0064	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0065	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0066	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0067	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0068	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0069	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0070	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0071	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0072	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0073	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0074	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0075	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0076	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0077	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0078	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0079	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0080	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0081	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0082	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0083	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0084	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0085	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0086	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0087	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0088	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0089	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0090	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0091	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0092	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0093	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0094	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0095	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0096	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0097	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0098	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0099	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL
0100	SPC-CA REVISION PACKAGE	15/04/2025	AL	AL	AL

NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
4. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS
Architect HAMES SHARLEY
Services AURECON
Structural PRITCHARD FRANCIS
PRINCIPAL CONTRACTOR
CLIENT
NEXTDC
NEXTDC
GPO Box 1219
Brisbane QLD 4001
T: +61 7 3177 4777
Contractor / Consultant / Document Author
Hames Sharley
Document Author Project Number
Key Plan
Site Stage NEXTDC Project Number
D2 0101 D1.0004
Project Address
2 RYKO CT (LOT 9704) &
6 RYKO CT (LOT 9703),
DARWIN CITY, 8000,
NORTHERN TERRITORY
Project Name
NEXTDC D2 STAGE 1
Drawing Title
LEVEL 3 FLOOR PLAN
Drawing Status
SPATIAL COORDINATION
FOR INFORMATION
DRAWN
HSA
03/02/2025
CHECKED
HSA
03/02/2025
APPD
HSA
03/02/2025
Scale Sheet File Name
1:100 A1 D2-ARC-HSA-PCA-A-0100-BUILDING
Dwg No. Rev
D2-ARC-HSA-PCA-A-0100-3103 SPC-6



NO.	DESCRIPTION	DATE	BY	CHKD	APPD
0001	SPC-DA PACKAGE- AMENDMENTS	15/03/2025	AL	AL	AL
0002	SPC-DA PACKAGE	14/03/2025	AL	AL	AL
0003	SPC-DA REVER PACKAGE	13/03/2025	AL	AL	AL
0004	SPC-DA REVER PACKAGE	12/03/2025	AL	AL	AL
0005	SPC-DA REVER PACKAGE	11/03/2025	AL	AL	AL
0006	SPC-DA REVER PACKAGE	10/03/2025	AL	AL	AL
0007	SPC-DA REVER PACKAGE	09/03/2025	AL	AL	AL
0008	SPC-DA REVER PACKAGE	08/03/2025	AL	AL	AL
0009	SPC-DA REVER PACKAGE	07/03/2025	AL	AL	AL
0010	SPC-DA REVER PACKAGE	06/03/2025	AL	AL	AL
0011	SPC-DA REVER PACKAGE	05/03/2025	AL	AL	AL
0012	SPC-DA REVER PACKAGE	04/03/2025	AL	AL	AL
0013	SPC-DA REVER PACKAGE	03/03/2025	AL	AL	AL
0014	SPC-DA REVER PACKAGE	02/03/2025	AL	AL	AL
0015	SPC-DA REVER PACKAGE	01/03/2025	AL	AL	AL
0016	SPC-DA REVER PACKAGE	31/02/2025	AL	AL	AL
0017	SPC-DA REVER PACKAGE	30/02/2025	AL	AL	AL
0018	SPC-DA REVER PACKAGE	29/02/2025	AL	AL	AL
0019	SPC-DA REVER PACKAGE	28/02/2025	AL	AL	AL
0020	SPC-DA REVER PACKAGE	27/02/2025	AL	AL	AL
0021	SPC-DA REVER PACKAGE	26/02/2025	AL	AL	AL
0022	SPC-DA REVER PACKAGE	25/02/2025	AL	AL	AL
0023	SPC-DA REVER PACKAGE	24/02/2025	AL	AL	AL
0024	SPC-DA REVER PACKAGE	23/02/2025	AL	AL	AL
0025	SPC-DA REVER PACKAGE	22/02/2025	AL	AL	AL
0026	SPC-DA REVER PACKAGE	21/02/2025	AL	AL	AL
0027	SPC-DA REVER PACKAGE	20/02/2025	AL	AL	AL
0028	SPC-DA REVER PACKAGE	19/02/2025	AL	AL	AL
0029	SPC-DA REVER PACKAGE	18/02/2025	AL	AL	AL
0030	SPC-DA REVER PACKAGE	17/02/2025	AL	AL	AL
0031	SPC-DA REVER PACKAGE	16/02/2025	AL	AL	AL
0032	SPC-DA REVER PACKAGE	15/02/2025	AL	AL	AL
0033	SPC-DA REVER PACKAGE	14/02/2025	AL	AL	AL
0034	SPC-DA REVER PACKAGE	13/02/2025	AL	AL	AL
0035	SPC-DA REVER PACKAGE	12/02/2025	AL	AL	AL
0036	SPC-DA REVER PACKAGE	11/02/2025	AL	AL	AL
0037	SPC-DA REVER PACKAGE	10/02/2025	AL	AL	AL
0038	SPC-DA REVER PACKAGE	09/02/2025	AL	AL	AL
0039	SPC-DA REVER PACKAGE	08/02/2025	AL	AL	AL
0040	SPC-DA REVER PACKAGE	07/02/2025	AL	AL	AL
0041	SPC-DA REVER PACKAGE	06/02/2025	AL	AL	AL
0042	SPC-DA REVER PACKAGE	05/02/2025	AL	AL	AL
0043	SPC-DA REVER PACKAGE	04/02/2025	AL	AL	AL
0044	SPC-DA REVER PACKAGE	03/02/2025	AL	AL	AL
0045	SPC-DA REVER PACKAGE	02/02/2025	AL	AL	AL
0046	SPC-DA REVER PACKAGE	01/02/2025	AL	AL	AL
0047	SPC-DA REVER PACKAGE	31/01/2025	AL	AL	AL
0048	SPC-DA REVER PACKAGE	30/01/2025	AL	AL	AL
0049	SPC-DA REVER PACKAGE	29/01/2025	AL	AL	AL
0050	SPC-DA REVER PACKAGE	28/01/2025	AL	AL	AL
0051	SPC-DA REVER PACKAGE	27/01/2025	AL	AL	AL
0052	SPC-DA REVER PACKAGE	26/01/2025	AL	AL	AL
0053	SPC-DA REVER PACKAGE	25/01/2025	AL	AL	AL
0054	SPC-DA REVER PACKAGE	24/01/2025	AL	AL	AL
0055	SPC-DA REVER PACKAGE	23/01/2025	AL	AL	AL
0056	SPC-DA REVER PACKAGE	22/01/2025	AL	AL	AL
0057	SPC-DA REVER PACKAGE	21/01/2025	AL	AL	AL
0058	SPC-DA REVER PACKAGE	20/01/2025	AL	AL	AL
0059	SPC-DA REVER PACKAGE	19/01/2025	AL	AL	AL
0060	SPC-DA REVER PACKAGE	18/01/2025	AL	AL	AL
0061	SPC-DA REVER PACKAGE	17/01/2025	AL	AL	AL
0062	SPC-DA REVER PACKAGE	16/01/2025	AL	AL	AL
0063	SPC-DA REVER PACKAGE	15/01/2025	AL	AL	AL
0064	SPC-DA REVER PACKAGE	14/01/2025	AL	AL	AL
0065	SPC-DA REVER PACKAGE	13/01/2025	AL	AL	AL
0066	SPC-DA REVER PACKAGE	12/01/2025	AL	AL	AL
0067	SPC-DA REVER PACKAGE	11/01/2025	AL	AL	AL
0068	SPC-DA REVER PACKAGE	10/01/2025	AL	AL	AL
0069	SPC-DA REVER PACKAGE	09/01/2025	AL	AL	AL
0070	SPC-DA REVER PACKAGE	08/01/2025	AL	AL	AL
0071	SPC-DA REVER PACKAGE	07/01/2025	AL	AL	AL
0072	SPC-DA REVER PACKAGE	06/01/2025	AL	AL	AL
0073	SPC-DA REVER PACKAGE	05/01/2025	AL	AL	AL
0074	SPC-DA REVER PACKAGE	04/01/2025	AL	AL	AL
0075	SPC-DA REVER PACKAGE	03/01/2025	AL	AL	AL
0076	SPC-DA REVER PACKAGE	02/01/2025	AL	AL	AL
0077	SPC-DA REVER PACKAGE	01/01/2025	AL	AL	AL
0078	SPC-DA REVER PACKAGE	31/12/2024	AL	AL	AL
0079	SPC-DA REVER PACKAGE	30/12/2024	AL	AL	AL
0080	SPC-DA REVER PACKAGE	29/12/2024	AL	AL	AL
0081	SPC-DA REVER PACKAGE	28/12/2024	AL	AL	AL
0082	SPC-DA REVER PACKAGE	27/12/2024	AL	AL	AL
0083	SPC-DA REVER PACKAGE	26/12/2024	AL	AL	AL
0084	SPC-DA REVER PACKAGE	25/12/2024	AL	AL	AL
0085	SPC-DA REVER PACKAGE	24/12/2024	AL	AL	AL
0086	SPC-DA REVER PACKAGE	23/12/2024	AL	AL	AL
0087	SPC-DA REVER PACKAGE	22/12/2024	AL	AL	AL
0088	SPC-DA REVER PACKAGE	21/12/2024	AL	AL	AL
0089	SPC-DA REVER PACKAGE	20/12/2024	AL	AL	AL
0090	SPC-DA REVER PACKAGE	19/12/2024	AL	AL	AL
0091	SPC-DA REVER PACKAGE	18/12/2024	AL	AL	AL
0092	SPC-DA REVER PACKAGE	17/12/2024	AL	AL	AL
0093	SPC-DA REVER PACKAGE	16/12/2024	AL	AL	AL
0094	SPC-DA REVER PACKAGE	15/12/2024	AL	AL	AL
0095	SPC-DA REVER PACKAGE	14/12/2024	AL	AL	AL
0096	SPC-DA REVER PACKAGE	13/12/2024	AL	AL	AL
0097	SPC-DA REVER PACKAGE	12/12/2024	AL	AL	AL
0098	SPC-DA REVER PACKAGE	11/12/2024	AL	AL	AL
0099	SPC-DA REVER PACKAGE	10/12/2024	AL	AL	AL
0100	SPC-DA REVER PACKAGE	09/12/2024	AL	AL	AL
0101	SPC-DA REVER PACKAGE	08/12/2024	AL	AL	AL
0102	SPC-DA REVER PACKAGE	07/12/2024	AL	AL	AL
0103	SPC-DA REVER PACKAGE	06/12/2024	AL	AL	AL
0104	SPC-DA REVER PACKAGE	05/12/2024	AL	AL	AL
0105	SPC-DA REVER PACKAGE	04/12/2024	AL	AL	AL
0106	SPC-DA REVER PACKAGE	03/12/2024	AL	AL	AL
0107	SPC-DA REVER PACKAGE	02/12/2024	AL	AL	AL
0108	SPC-DA REVER PACKAGE	01/12/2024	AL	AL	AL
0109	SPC-DA REVER PACKAGE	30/11/2024	AL	AL	AL
0110	SPC-DA REVER PACKAGE	29/11/2024	AL	AL	AL
0111	SPC-DA REVER PACKAGE	28/11/2024	AL	AL	AL
0112	SPC-DA REVER PACKAGE	27/11/2024	AL	AL	AL
0113	SPC-DA REVER PACKAGE	26/11/2024	AL	AL	AL
0114	SPC-DA REVER PACKAGE	25/11/2024	AL	AL	AL
0115	SPC-DA REVER PACKAGE	24/11/2024	AL	AL	AL
0116	SPC-DA REVER PACKAGE	23/11/2024	AL	AL	AL
0117	SPC-DA REVER PACKAGE	22/11/2024	AL	AL	AL
0118	SPC-DA REVER PACKAGE	21/11/2024	AL	AL	AL
0119	SPC-DA REVER PACKAGE	20/11/2024	AL	AL	AL
0120	SPC-DA REVER PACKAGE	19/11/2024	AL	AL	AL
0121	SPC-DA REVER PACKAGE	18/11/2024	AL	AL	AL
0122	SPC-DA REVER PACKAGE	17/11/2024	AL	AL	AL
0123	SPC-DA REVER PACKAGE	16/11/2024	AL	AL	AL
0124	SPC-DA REVER PACKAGE	15/11/2024	AL	AL	AL
0125	SPC-DA REVER PACKAGE	14/11/2024	AL	AL	AL
0126	SPC-DA REVER PACKAGE	13/11/2024	AL	AL	AL
0127	SPC-DA REVER PACKAGE	12/11/2024	AL	AL	AL
0128	SPC-DA REVER PACKAGE	11/11/2024	AL	AL	AL
0129	SPC-DA REVER PACKAGE	10/11/2024	AL	AL	AL
0130	SPC-DA REVER PACKAGE	09/11/2024	AL	AL	AL
0131	SPC-DA REVER PACKAGE	08/11/2024	AL	AL	AL
0132	SPC-DA REVER PACKAGE	07/11/2024	AL	AL	AL
0133	SPC-DA REVER PACKAGE	06/11/2024	AL	AL	AL
0134	SPC-DA REVER PACKAGE	05/11/2024	AL	AL	AL
0135	SPC-DA REVER PACKAGE	04/11/2024	AL	AL	AL
0136	SPC-DA REVER PACKAGE	03/11/2024	AL	AL	AL
0137	SPC-DA REVER PACKAGE	02/11/2024	AL	AL	AL
0138	SPC-DA REVER PACKAGE	01/11/2024	AL	AL	AL
0139	SPC-DA REVER PACKAGE	31/10/2024	AL	AL	AL
0140	SPC-DA REVER PACKAGE	30/10/2024	AL	AL	AL
0141	SPC-DA REVER PACKAGE	29/10/2024	AL	AL	AL
0142	SPC-DA REVER PACKAGE	28/10/2024	AL	AL	AL
0143	SPC-DA REVER PACKAGE	27/10/2024	AL	AL	AL
0144	SPC-DA REVER PACKAGE	26/10/2024	AL	AL	AL
0145	SPC-DA REVER PACKAGE	25/10/2024	AL	AL	AL
0146	SPC-DA REVER PACKAGE	24/10/2024	AL	AL	AL
0147	SPC-DA REVER PACKAGE	23/10/2024	AL	AL	AL
0148	SPC-DA REVER PACKAGE	22/10/2024	AL	AL	AL
0149	SPC-DA REVER PACKAGE	21/10/2024	AL	AL	AL
0150	SPC-DA REVER PACKAGE	20/10/2024	AL	AL	AL
0151	SPC-DA REVER PACKAGE	19/10/2024	AL	AL	AL
0152	SPC-DA REVER PACKAGE	18/10/2024	AL	AL	AL
0153	SPC-DA REVER PACKAGE	17/10/2024	AL	AL	AL
0154	SPC-DA REVER PACKAGE	16/10/2024	AL	AL	AL
0155	SPC-DA REVER PACKAGE	15/10/2024	AL	AL	AL
0156	SPC-DA REVER PACKAGE	14/10/2024	AL	AL	AL
0157	SPC-DA REVER PACKAGE	13/10/2024	AL	AL	AL
0158	SPC-DA REVER PACKAGE	12/10/2024	AL	AL	AL
0159	SPC-DA REVER PACKAGE	11/10/2024	AL	AL	AL
0160	SPC-DA REVER PACKAGE	10/10/2024	AL	AL	AL
0161	SPC-DA REVER PACKAGE	09/10/2024	AL	AL	AL
0162	SPC-DA REVER PACKAGE	08/10/2024	AL	AL	AL
0163	SPC-DA REVER PACKAGE	07/10/2024	AL	AL	AL
0164	SPC-DA REVER PACKAGE	06/10/2024	AL	AL	AL
0165	SPC-DA REVER PACKAGE	05/10/2024	AL	AL	AL
0166	SPC-DA REVER PACKAGE	04/10/2024	AL	AL	AL
0167	SPC-DA REVER PACKAGE	03/10/2024	AL	AL	AL
0168	SPC-DA REVER PACKAGE	02/10/2024	AL	AL	AL
0169	SPC-DA REVER PACKAGE	01/10/2024	AL	AL	AL
0170	SPC-DA REVER PACKAGE	30/09/2024	AL	AL	AL
0171	SPC-DA REVER PACKAGE	29/09/2024	AL	AL	AL
0172	SPC-DA REVER PACKAGE	28/09/2024	AL	AL	AL
0173	SPC-DA REVER PACKAGE	27/09/2024	AL	AL	AL
0174	SPC-DA REVER PACKAGE	26/09/2024	AL	AL	AL
0175	SPC-DA REVER PACKAGE	25/09/2024	AL	AL	AL
0176	SPC-DA REVER PACKAGE	24/09/2024	AL	AL	AL
0177	SPC-DA REVER PACKAGE	23/09/2024	AL	AL	AL
0178	SPC-DA REVER PACKAGE	22/09/2024	AL	AL	AL
0179	SPC-DA REVER PACKAGE	21/09/2024	AL	AL	AL
0180	SPC-DA REVER PACKAGE	20/09/2024	AL	AL	AL
0181	SPC-DA REVER PACKAGE	19/09/2024	AL	AL	AL
0182	SPC-DA REVER PACKAGE	18/09/2024	AL	AL	AL
0183	SPC-DA REVER PACKAGE	17/09/2024	AL	AL	AL
0184	SPC-DA REVER PACKAGE	16/09/2024	AL	AL	AL
0185	SPC-DA REVER PACKAGE	15/09/2024	AL	AL	AL
0186	SPC-DA REVER PACKAGE	14/09/2024	AL	AL	AL
0187	SPC-DA REVER PACKAGE	13/09/2024	AL	AL	AL
0188	SPC-DA REVER PACKAGE	12/09/2024	AL	AL	AL
0189	SPC-DA REVER PACKAGE	11/09/2024	AL	AL	AL
0190	SPC-DA REVER PACKAGE	10/09/2024	AL	AL	AL
0191	SPC-DA REVER PACKAGE	09/09/2024	AL	AL	AL
0192	SPC-DA REVER PACKAGE	08/09/2024	AL	AL	AL
0193	SPC-DA REVER PACKAGE	07/09/2024	AL	AL	AL
0194	SPC-DA REVER PACKAGE	06/09/2024	AL	AL	AL
0195	SPC-DA REVER PACKAGE	05/09/2024	AL	AL	AL
0196	SPC-DA REVER PACKAGE	04/09/2024	AL	AL	AL
0197	SPC-DA REVER PACKAGE	03/09/2024	AL	AL	AL
0198	SPC-DA REVER PACKAGE	02/09/2024	AL	AL	AL
0199	SPC-DA REVER PACKAGE	01/09/2024	AL	AL	AL
0200	SPC-DA REVER PACKAGE	31/08/2024	AL	AL	AL
0201	SPC-DA REVER PACKAGE	30/08/2024	AL	AL	AL
0202	SPC-DA REVER PACKAGE	29/0			




WEATHERPROOF
ALUMINIUM LOUVERS




WHITE CONCRETE PANELS
WITH NEXTDC SIGNANCE




GLAZING WITH ALUMINIUM
FRAME IN MONUMENT




NORTH ELEVATION - RYKO CT
1:200



EAST ELEVATION - STAGE 1/PARK
1:200



ALUMINIUM RISER SCREEN
TO MATCH NEXTDC STAGE 1



CONCRETE PANELS WITH
COLOURED/GREY ADDITIVES



ARTWORK TO EXTERNAL STORAGE
TANKS - ARTIST AND ARTWORK TO BE
APPROVED. ARTWORK SHOWN AS AN
EXAMPLE.

02/02/2025	SPC-6	PACKAGE AMENDMENTS	HSA	ALL	HSA
14/07/2024	SPC-6	PACKAGE	HSA	ALL	HSA
21/01/2024	SPC-6	REVIEW PACKAGE	HSA	ALL	HSA
08/01/2024	SPC-6	REVIEW PACKAGE	HSA	ALL	HSA
20/12/2023	SPC-6	REVIEW PACKAGE	HSA	ALL	HSA
11/03/2024	SPC-6	DEVELOPMENT APPLICATION PACKAGE	HSA	ALL	HSA
08/03/2024	SPC-6	FOR INFORMATION	HSA	ALL	HSA
08/03/2024	SPC-6	FOR INFORMATION	HSA	ALL	HSA
18/10/24	SPC-6	FOR INFORMATION	HSA	ALL	HSA
DATE	REV	DESCRIPTION	BY	CHK	APP

NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
4. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS
Architect HAMES SHARLEY
Services AURECON
Structural PRITCHARD FRANCIS

PRINCIPAL CONTRACTOR

CLIENT

NEXTDC
GPO Box 1219
Brisbane QLD 4001
T: +61 7 3177 4777
(Contractor / Consultant / Document Author)

Document Author Project Number

Key Plan

Site	Stage	NEXTDC Project Number
D2	0101	D1.0004

Project Address
2 RYKO CT (LOT 9704) &
6 RYKO CT (LOT 9703),
DARWIN CITY, 8000,
NORTHERN TERRITORY

Project Name
NEXTDC D2 STAGE 1

Drawing Title
ELEVATIONS SHEET 1

Drawing Status
SPATIAL COORDINATION
FOR INFORMATION


DRAWN	HSA	DATE	03/02/2025
CHECKED	AD	DATE	03/02/2025
APPROVED	JLS	DATE	03/02/2025

Scale	Sheet	File Name
As indicated A1	02-ARC-HSA-PDA-A-001-BUILDING	

Drawn by	Rev
D2-ARC-HSA-ORG-A-0100-7000	SPC-6




WEATHERPROOF
ALUMINIUM LOUVERS




GLAZING WITH ALUMINIUM
FRAME IN MONUMENT



WHITE CONCRETE PANELS
WITH NEXTDC SIGNAGE




SOUTH ELEVATION - GARRAMILLA BVD.
1: 200




ALUMINIUM RISER SCREEN
TO MATCH NEXTDC STAGE 1



ARTWORK TO EXTERNAL STORAGE
TANKS - ARTIST AND ARTWORK TO BE
APPROVED. ARTWORK SHOWN AS AN
EXAMPLE.



WEST ELEVATION - HARVEY ST.
1: 200



CONCRETE PANELS WITH
COLOURED/GREY ADDITIVES

10/01/2023	SPC-01	PACKAGE AMENDMENTS	150A	ALL	150A
14/01/2023	SPC-02	PACKAGE	150A	ALL	150A
21/01/2023	SPC-03	PACKAGE REVISION PACKAGE	150A	ALL	150A
28/01/2023	SPC-04	PACKAGE REVISION PACKAGE	150A	ALL	150A
28/01/2023	SPC-05	PACKAGE REVISION PACKAGE	150A	ALL	150A
11/02/2023	SPC-06	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-07	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-08	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-09	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-10	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-11	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-12	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-13	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-14	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-15	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-16	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-17	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-18	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-19	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-20	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-21	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-22	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-23	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-24	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-25	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-26	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-27	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-28	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-29	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-30	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-31	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-32	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-33	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-34	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-35	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-36	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-37	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-38	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-39	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-40	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-41	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-42	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-43	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-44	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-45	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-46	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-47	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-48	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-49	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-50	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-51	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-52	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-53	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-54	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-55	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-56	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-57	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-58	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-59	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-60	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-61	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-62	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-63	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-64	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-65	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-66	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-67	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-68	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-69	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-70	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-71	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-72	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-73	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-74	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-75	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-76	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-77	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-78	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-79	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-80	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-81	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-82	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-83	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-84	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-85	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-86	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-87	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-88	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-89	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-90	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-91	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-92	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-93	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-94	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-95	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-96	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-97	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-98	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-99	PACKAGE REVISION PACKAGE	150A	ALL	150A
15/02/2023	SPC-100	PACKAGE REVISION PACKAGE	150A	ALL	150A

NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
4. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS
Architect HAMES SHARLEY
Services AURECON
Structural PRITCHARD FRANCIS

PRINCIPAL CONTRACTOR


CLIENT



NEXTDC
GPO Box 12119
Brisbane QLD 4001
T: +61 7 3177 4777
(Contractor / Consultant / Document Author)

Hames Sharley
Document Author Project Number

Key Plan



Site D2 Stage 0101 NEXTDC Project Number D1.0004

Project Address
2 RYKO CT (LOT 9704) &
6 RYKO CT (LOT 9703),
DARWIN CITY, 8000,
NORTHERN TERRITORY

Project Name
NEXTDC D2 STAGE 1

Drawing Title
ELEVATIONS SHEET 2

Drawing Status
SPATIAL COORDINATION
FOR INFORMATION

Drawn	Check	Rev
15/02/2023	15/02/2023	15/02/2023
Drawn	Check	Rev
15/02/2023	15/02/2023	15/02/2023


Scale Sheet File Name
As indicated A1 02-ARC-HSA-PCA-A-0101-BUILDING

Drawn by: 15/02/2023
Rev: 15/02/2023

D2-ARC-HSA-PCA-A-0101-7001 SPC-6



SOUTH STREET ELEVATION - GARRAMILLA BVD.
1 : 500



WEST STREET ELEVATION - HARVEY ST.
1 : 500



NORTH STREET ELEVATION - RYKO CRT
1 : 500



EAST STREET ELEVATION - STAGE 1/PARK
1 : 500

02/02/2025	SPC	DA PACKAGE - AMENDMENTS	HSA	AL	HSA
24/07/2025	SPC	DA PACKAGE	HSA	AL	HSA
21/01/2025	SPC	DA REVISION PACKAGE	HSA	AL	HSA
08/01/2025	SPC	DA REVISION PACKAGE	HSA	AL	HSA
28/12/2024	SPC	DA REVISION PACKAGE	HSA	AL	HSA
11/03/2024	SPC	DEVELOPMENT APPLICATION PACKAGE	HSA	AL	HSA
08/03/2024	D	FOR INFORMATION	HSA	AL	HSA
08/03/2024	D	FOR INFORMATION	HSA	AL	HSA
18/10/24	D	FOR INFORMATION	HSA	AL	HSA
DATE	REV	DESCRIPTION / REVISION	DESIGN	DATE	BY

- NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
 2. DO NOT SCALE FROM DRAWINGS
 3. CONFIRM ALL MEASUREMENTS ON SITE
 4. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
 5. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS

Architect HAMES SHARLEY

Services AURECON

Structural PRITCHARD FRANCIS

PRINCIPAL CONTRACTOR

CLIENT




NEXTDC
GPO Box 3219
Brisbane QLD 4001
T: +61 7 3177 4777

[Contractor / Consultant / Document Author]
Hames Sharley

Document Author Project Number
hamessharley.com.au +61 8 9381 0200

Key Plan



Site	Stage	NEXTDC Project Number
D2	0101	D1.0004

Project Address
2 RYKO CT (LOT 9704) &
6 RYKO CT (LOT 9703),
DARWIN CITY, 8000,
NORTHERN TERRITORY

Project Name

NEXTDC D2 STAGE 1

Drawing Title

STREET ELEVATIONS

Drawing Status
SPATIAL COORDINATION
FOR INFORMATION

DRAWN	HSA	DATE	03/02/2025
CHECKED	AD	DATE	03/02/2025
APPROVED	JLS	DATE	03/02/2025

Scale	Sheet	File Name
1 : 500	A1	02-ARC-HSA-PCA-A-001-BUILDING

Drawn by	Rev
D2-ARC-HSA-PCA-A-0100-7100	SPC-6

design statement.



The proposed 6-megawatt data centre, located adjacent to the existing D1 facility on Ryko Court, Darwin, is designed to accommodate three levels of data halls.

The building integrates offices, indoor and outdoor breakout areas, with front-of-house components strategically along Ryko Court and Garamilla Boulevard. This maximises glazing along these frontages to create a dynamic and engaging streetscape.

At the ground level, visually permeable spaces foster passive surveillance and activate the extensive frontage along Garamilla Boulevard and Harvey Street.

An outdoor breakout terrace to the north establishes a meaningful connection to the surrounding landscape, offering occupants a functional and refreshing outdoor space.

To enhance pedestrian comfort and create a welcoming environment, an awning along Garamilla Boulevard provides shading for the ground floor office spaces while contributing to the building's human-scaled interface.

The façade employs patterned and coloured concrete to create an articulated aesthetic, subtly referencing the cladding of perforated aluminium on the existing D1 centre. Linear lighting highlights key architectural elements, while corporate branding and colours are used thoughtfully as wayfinding tools.

Vertical circulation elements are expressed from the primary building frontages, adding depth and articulation to the otherwise expansive facades.

The upper levels efficiently stack the data halls, with plant and equipment screened both acoustically and visually to minimize impact on neighbouring properties.

This design balances the functional requirements of a high-performing data centre with thoughtful architectural elements that enhance its urban presence, promote connectivity, and create a positive experience for both building users and the surrounding community.





DEVELOPMENT APPLICATION - LANDSCAPE

NEXT DC D2 STAGE 1

T.C.L

Hames
Sharley



P1 ISSUE - 16.01.2025

SITE CONTEXT

Ryko Court, Darwin

CONNECTION TO COUNTRY

We acknowledge the ancestral lands of the Larrakia people and pay respects to elders past, present and emerging.

Traditional Owners across Australia are the original custodians of our land and waters, and we recognise ongoing and unique care for country and a deep spiritual connection to it. The knowledge and wisdom of Traditional Owners has, and will, ensure the continuation of cultures and traditional practices and enrich our ongoing understanding and interpretation of place.

And, importantly, we hope this shared caring provides us with appropriate and considerate ways of working On Country in all our practice endeavours.



LOCATION



SITE CONTEXT


Ryko Court, Darwin

KEY CONSIDERATIONS




SITE CONCEPT

Landscape Design



SITE CONCEPT

Landscape Design




SITE CONCEPT


Landscape Design

SPATIAL DIAGRAM


GROUND FLOOR
& Planting Zones



BASEMENT



SOFTSCAPE TAKE-OFF



Key

Planting

- 1 Entrance Planting
- 2 Street interface (Ryko/ Harvey)
- 3 Garramilla Interface
- 4 Terrace Planting

Hard Elements

- Next DC Feature Balustrade
- Steel Blade Wall
- Steel Balustrade
- Broom finished concrete

Key

Softscape Areas

- A Harvey Frontage = 156.0 m²
- B Ryko Frontage = 87.9 m²
- C Balcony Planters = 7.6 m²
- D St1 / St2 Garden = 78.5 m²
- E Garramilla Frontage = 45.2 m²

TOTAL PLANTING AREA = 375 M²

SITE CONCEPT

Landscape Palettes

PLANTING

1 Entrance Planting



Syzygium Armstrongii



Hibiscus tiliaceus rubra, Red Beach Hibiscus



Molineria capitulata, NT Palm Grass



Leea novoguineensis, Bandicoot Berry



Stenochlaena palustris, Climbing Swamp Fern

2 Street Interface (Harvey / Ryko)



Melaleuca viridiflora, Broad-Leaved Paperbark



Zoysia sp. Lawn



Triodia pungens, Soft Spinifex



Grevillea formosa, Mt Brockman



Ipomoea pes-caprae, (Beach Morning Glory)

3 Garramilla Interface



Zoysia sp. Lawn



Gardenia psidioides, 'Glennie River'



Hymenocallis littoralis, Spider Lily

4 Terrace Planting



Gardenia psidioides, 'Glennie River'



Vitex rotundifolia, Beach Vitex



Melaleuca incana 'Velvet Cushion',
Honey-Myrtle Cultivar



Sansevieria zeylanica, Snake Plant



Capparis spinosa, Caper Bush

SITE CONCEPT

Landscape Palettes

HARDSCAPE ELEMENTS

Pavement



Continous Broom Finish to Concrete
(to match Stage One)



Compacted Rubble pathways



Timber Battens on Concrete seating element
with rubble pavement and tree plantings



Hardwood Timber Battens - New



Pre-cast Concrete Footings - Existing reused


Balustrade And Barriers



Black Painted Steel
- Blade Wall (Solid) / Balustrade (to match Stage One)



Black Palisade Security Fencing



Next DC Feature Fence
(to match Stage One Garramilla fontage)



Optional Mesh Screen TBC
(to Ryko Court frontage services entrances)

Vertical planting elements



Mesh Screen with Climbers



Vertical Planting on wires



Garramilla Stone precedent



NEXTDC D2 Stage 1

Acoustic Report

NEXTDC Pty Ltd

Reference: P526971

Revision:

2025-01-28

Document control record

Document prepared by:

Aurecon Australasia Pty Ltd

ABN 54 005 139 873

Aurecon Centre

Level 8, 850 Collins Street

Docklands, Melbourne VIC 3008

PO Box 23061

Docklands VIC 8012

Australia

T +61 3 9975 3000

F +61 3 9975 3444

E melbourne@aurecongroup.com

W aurecongroup.com

A person using Aurecon documents or data accepts the risk of:

- a) Using the documents or data in electronic form without requesting and checking them for accuracy against the original hard copy version.
- b) Using the documents or data for any purpose not agreed to in writing by Aurecon.

Document control		aurecon				
Report title		Acoustic Report				
Document code			Project number		P526971	
File path		Https://aurecongroup.sharepoint.com/sites/BuildingSciences/Shared Documents/Acoustics/04 Projects/NextDC D1/Reports/526971-0000-REP-MA-01[1] NEXTDC D2 Stage 1 DA Acoustic Report.docx				
Client		NEXTDC Pty Ltd				
Client contact			Client reference			
Rev	Date	Revision details/status	Author	Reviewer	Verifier (if required)	Approver
1	2025-01-28	Revision 1	CZ	HM		
Current revision						

Approval			
Author signature		Approver signature	
Name	Chris Zhang	Name	
Title	Acoustic Engineer	Title	

Contents

1	Introduction.....	2
2	Existing environment	2
2.1	Existing background noise levels	2
3	Noise Regulation	4
3.1	Northern Territory noise management framework guidelines	4
3.1.1	Project intrusiveness noise level	4
3.1.2	Project amenity noise level.....	4
3.1.3	Establishing project specific assigned noise level.....	5
3.2	Typical operation and emergency testing.....	5
3.3	Emergency operation	6
3.4	Recommended operational criteria	7
3.5	Construction noise	7
3.5.1	Recommended standard hours of construction work.....	7
3.5.2	Recommended construction noise levels	8
3.5.3	Project construction noise criteria	9
3.5.4	Construction noise impacts	9
4	Equipment Schedules	10
4.1	Existing D1 Stage 1 noise emissions	10
4.2	Equipment Schedules.....	10
4.2.1	Generator mitigation package	11
5	Noise modelling.....	12
5.1	Methodology	12
5.2	Noise Modelling	12
5.3	Assumptions and limitations	13
5.4	Results.....	13
6	Conclusion	14

Appendices

Noise Contours

Figures

Figure 1: Site overview

Figure 2 Logger Location

Figure 3 3D model of data centre building and surrounds

Tables

Table 3 Rating background level from NDY report

Table 1 Minimum assumed RBLs and project intrusiveness noise levels

Table 2 Recommended maximum assigned amenity noise levels

Table 4 Project Specific Environmental Noise Limits

Table 5 Recommended standard hours of work

Table 6 Recommended assigned construction noise levels for airborne noise at residential premises

Table 7 Recommended assigned noise levels for airborne noise at commercial and industrial premises

Table 8 Residential construction NML

Table 9 Non-residential construction NMLs

Table 10 D2 Stage1 Equipment Schedule

Table 11 Typical Operation noise emission predictions

Table 12 Generator Testing noise emission predictions

Executive Summary

Aurecon has been engaged by NEXTDC to undertake the design and environmental assessment of a proposed new data centre located at 2 – 6 Ryko Court, Darwin City, Northern Territory 0800. The project (NEXTDC D2 Stage 1) is located adjacent to the existing data centre (NEXTDC D1 Stage1) on 8 Ryko Court, Darwin City, Northern Territory 0800 however is located on a separate lot.

The site and nearest sensitive receivers are located within the Central Business Zone (Urban Residential Category). Land use in this surrounding area consists of residential apartment buildings and industry buildings.

Noise emissions from the proposed data centre have been assessed for two key operational scenarios as follows:

- Typical operation
- Emergency testing

Noise criteria have been established on the site based on the Northern Territory Noise Management Framework Guideline (NT Guideline). Typical operation of the site (including cooling and ventilation systems) is expected to be 24 hours per day 7 days per week, and therefore for normal operation compliance with the most onerous night period criteria is required. For routine generator maintenance and testing this would be scheduled to occur during the day only and therefore compliance with the day period criteria is required for the emergency testing operational scenario.

- Typical operation: a night criterion of 40 dBA would be the most stringent criterion and would dictate the noise mitigation for services plant equipment
- Emergency testing: emissions should achieve the day period criterion of 49 dBA.

A 3D computational noise model has been developed of the site and surrounding buildings using SoundPLAN v9.0. The model includes the neighbouring buildings and the topography of the surrounding area. The model incorporates the key items of noise generating equipment included in the design, such as cooling towers, fans and emergency backup generators. Noise emissions from the overall site has been predicted at the surrounding receivers based on the current concept design.

Based on the current design, compliance with the project specific environmental noise limits is predicted to be achieved. However, any future changes in noise emitting mechanical or electrical equipment selection or design will require additional acoustic assessment to be undertaken to ensure noise limits are met at all noise sensitive receivers at all time periods.

1 Introduction

Aurecon have been engaged by NEXTDC to provide acoustic design service on proposed D2 Stage 1 facility at 2 – 6 Ryko Court, Darwin City NT 0800. The project brief is for an 8MW IT data centre on the lot behind the existing D1 Stage 1 facility at 8 Ryko Court.

This report assesses the potential noise impacts from the operation of the proposed NEXTDC D2 Stage 1 site on nearby surrounding premises. The following scenarios are considered once the building is fully operational.

- Typical operation – regular services in operation
- Generator testing – regular services together with the testing of one generator and one load bank unit

2 Existing environment

The site is located at Ryko Court in Darwin City. The two closest noise receivers are residential apartment buildings as identified below:

- 3 Harvey St, Darwin City NT 0800
- 12-16 Harvey St, Darwin City NT 0800

An overview of the site is shown in Figure 1.




Figure 1: Site overview

2.1 Existing background noise levels

Noise logging was previously undertaken in the surrounding area by NDY as part of the NEXTDC D1 Stage 1 project (prior to the construction of the D1 datacentre). A noise logger was installed on the 24th of

August 2022 for two weeks to measure the background noise levels at a location representative of the nearest sensitive receiver at 12–16 Harvey St¹. The logger location is shown in Figure 2.




Figure 2 Logger Location

The Rating Background Level (RBL) for the following assessment periods is determined using the tenth percentile method:

- Day: Mon to Sat: 7am to 6pm, Sun & public holiday: 8am to 6pm
- Evening: Mon to Sun: 6pm to 10pm
- Night: Mon to Sat: 10pm to 7am, Sun & public holiday: 10pm to 8am

The summary of the rating background level (RBL) measured during the noise survey is shown in Table 1.

Table 1 Rating background level from NDY report

Period	Rating Background Level (RBL), L ₉₀ (dBA)
Day: Mon to Sat: 7am to 6pm Sun & public holiday: 8am to 6pm	44
Evening: Mon to Sun: 6pm to 10pm	44
Night: Mon to Sat: 10pm to 7am Sun & public holiday: 10pm to 8am	41

The existing substation to the south of the site is expected to be the dominant noise source in the area. Previous assessments from NDY report indicated that noise emissions from D1 stage 1 are expected to be below 36 dBA to the nearby residences. These measurements are therefore considered to be representative of the current noise environment on the site and appropriate to assess the background noise levels in the surrounding area for the purposes of assessing the potential impact of NEXTDC D2 Stage 1.

¹ NEXTDC Stage 1 Site Design Report (Acoustic Services), Revision 1, by NDY dated 26 September 2023

3 Noise Regulation

3.1 Northern Territory noise management framework guidelines

The Northern Territory Noise Management Framework Guideline (NT Guideline) provides guidance to assign noise levels for various types of emissions. The project specific assigned noise level is derived by considering its two components: intrusiveness noise level and amenity noise level.

3.1.1 Project intrusiveness noise level

The intrusiveness noise level seeks to limit the degree of change a new noise source introduces to an existing environment. A noise source would generally be considered non-intrusive if the monitored average noise level (L_{Aeq}) for a period does not exceed the rating background noise level (RBL) by more than 5 dB(A) and is summarised in equation below. Intrusive noise levels are only applied to residential receivers.

$$\text{Project Intrusiveness noise level } L_{Aeq,15min} = \text{rating background noise level} + 5 \text{ dB}$$

Table 2 provides a summary of minimum assumed RBLs and project intrusiveness noise levels. This represents the lowest applicable project intrusiveness noise levels where background noise levels have not been measured on site.

Table 2 Minimum assumed RBLs and project intrusiveness noise levels

Period	Min assumed rating background level (RBL), L_{90} (dBA)	Min project intrusiveness noise level ($L_{Aeq,15min}$) (dBA)
Day: Mon to Sat: 7am to 6pm Sun & public holiday: 8am to 6pm	35	40
Evening: Mon to Sun: 6pm to 10pm	30	35
Night: Mon to Sat: 10pm to 7am Sun & public holiday: 10pm to 8am	30	35

3.1.2 Project amenity noise level

To limit continuing increases in noise levels from application of the intrusiveness level alone, the ambient noise level within an area from all industrial noise sources combined should remain below the recommended amenity noise levels specified in Table 3 where feasible and reasonable.

For this project, all residential receivers have been identified as 'Urban' as they are in the Central Business (CB) zone. The recommended amenity noise levels are intended to protect against noise impacts such as speech interference, community annoyance and some sleep disturbance.

Since the night-time amenity noise criterion is the most stringent, it is the controlling time-period. To ensure that industrial noise levels remain within the recommended maximum assigned amenity noise levels for an area, a project specific amenity noise level applies for each new source of industrial noise as follows:

$$\text{Project Amenity noise level } L_{Aeq,15min} = \text{recommended amenity noise level} - 5 \text{ dB}$$

Table 3 Recommended maximum assigned amenity noise levels

Receiver	Noise amenity area	Time of the day	Recommended maximum assigned amenity noise level, $L_{Aeq,dBA}$
Residential	Urban	Day	60
		Evening	50
		Night	45
Industrial premises	All	When in use	70

3.1.3 Establishing project specific assigned noise level

The project specific assigned noise level reflects the most stringent noise level requirement from the noise levels derived from both the project intrusiveness noise level and project specific amenity noise level. They set the benchmark against which noise impacts and the need for noise mitigation are assessed. Applying the most stringent requirement as the project specific assigned noise level ensures that both intrusive noise is limited, and amenity is protected.

3.2 Typical operation and emergency testing

Based on Section 3.1 and the measured RBLs in Section 2.1, a summary of the project specific assigned noise levels is derived in Table 4 below.

Table 4 Project Specific Environmental Noise Limits

Period	Measured Rating Background Level (RBL), L_{90} (dBA)	Project Intrusiveness Noise Level $L_{Aeq,15min}$ (dBA)	Project Specific Amenity Noise Level for Industrial Development (dBA)	Project Specific Assigned Noise Level (dBA)
Day: Mon to Sat: 7am to 6pm Sun & public holiday: 8am to 6pm	44	49	55	49
Evening: Mon to Sun: 6pm to 10pm	44	49	45	45
Night: Mon to Sat: 10pm to 7am Sun & public holiday: 10pm to 8am	41	46	40	40

Typical operation of the NEXTDC D2 Stage 1 datacentre facility will consist of all services plant equipment with the exception of the generators operating continuously 24 hours, 7 days a week. Therefore, the combined typical operational noise emitted by all equipment from the data centre facility should be designed to achieve the worst-case night period limit, i.e.: L_{Aeq} 40dBA at the adjacent residential boundaries.

Routine testing of the emergency backup generators would be scheduled to occur during the day period only. This would generally consist of the operation of a single generator unit together with a load bank unit. As this testing would be scheduled to occur during the day period, noise emissions should be designed to achieve the day period limit, i.e. L_{Aeq} 49 dBA.

3.3 Emergency operation

The NT Noise Management Framework Guideline does not provide any guidance on expected criteria for noise emissions from back-up diesel generators that would only be used infrequently for maintenance and testing or in the event of a power failure.

The NSW Noise Policy for Industry (NPfI) which the NT Noise Management Framework Guideline is based on also does not provide criteria for the operation of generators used in the event of an emergency. As this type of event is rare and the impact would typically of short duration (less than one day), it is not 'feasible and reasonable' as defined in NPfI to design the noise emission from the generators to specific target noise levels.

The NPfI also notes that the criteria apply only to activities described in Schedule 1 of the Protection of the Environment Operations (POEO) Act. Under the 'Electricity generation' section, it states that the clause is not applicable to '*the generation of electricity by means of electricity plant that is emergency stand-by plant operating for less than 200 hours per year*' which would apply in this case for generation during critical power failure.

On this basis it is considered that noise limits should not be applied to emissions during the emergency operation mode. However reasonable and practicable measures should be implemented to reduce noise emissions where feasible.

3.4 Recommended operational criteria

A review of the applicable NT regulations concerning environmental noise emissions has been undertaken. The following criteria are proposed for the three identified operational scenarios.

- For typical operational noise emissions, which does not include generator operation, a night criterion of L_{Aeq} 40 dBA would be the most stringent criterion and would dictate the noise mitigation for services plant equipment only.
- For generator testing, it is possible that a cumulative 200 hours of operational time per year may be exceeded. It is therefore recommended that testing should be limited to day periods only, and emissions should achieve the day period criterion of 49 dBA based on the methodology set out in NSW NPfI. We understand that testing would involve one generator at a time with a load bank.
- For emergency operations, it is proposed that the approach adopted in NSW is applied where no specific limit is applied to emergency operation. It is recommended that reasonable measures should be put in place to reduce noise from generators as far as is considered practical.

3.5 Construction noise

The Northern Territory Noise Management Framework Guideline (NT Guideline) applies to the management of construction noise in North Territory (NT). This guideline provides recommendations on standard construction hours and construction noise management levels (NMLs).

3.5.1 Recommended standard hours of construction work

Section 3.3.2 of the NT Guideline recommends standard hours for construction work as shown in Table 5:

Table 5 Recommended standard hours of work

Work type	Recommended standard hours of work
Normal construction	Monday to Saturday: 7am to 7pm and between 9am and 6pm Sundays or public holidays
Blasting	Monday to Friday: 9am to 5pm Saturday 9am to 1pm No blasting on Sundays or public holidays

NT Guideline notes that the recommended standard hours of work are not mandatory and acknowledge that some activities could be undertaken outside of the recommended standard hours of work, assuming all feasible and reasonable mitigation measurement are implemented to minimise impacts of surrounding sensitive land uses. These activities include:

- The delivery of oversized plant or structures that police or other authorities determine require special arrangements to transport along public roads
- Emergency work to avoid the loss of life or damage to property, or to prevent environmental harm
- Maintenance and repair of public infrastructure where disruption to essential services and/or considerations of worker safety do not allow work within standard hours
- Public infrastructure works that shorten the length of the project and are supported by the affected community, or
- Works where a proponent demonstrates and justifies a need to operate outside the recommended standard hours

3.5.2 Recommended construction noise levels

Recommended assigned construction noise levels for residential and non-residential receivers are presented in Table 6 and Table 7 respectively.

Table 6 Recommended assigned construction noise levels for airborne noise at residential premises

Descriptor	Recommended assigned construction noise level at residences $L_{Aeq}(15min)$	How to apply
Monday to Saturday 7am to 7pm Sundays and public holidays 9am to 6pm	Recommended assigned noise affected level: $RBL^1 + 10 \text{ dB}$	The recommended assigned noise affected level represents the point above which there may be some community reaction to noise. Where the predicted or measured $L_{Aeq}(15min)$ is greater than recommended assigned noise affected level, proponents should apply all feasible and reasonable work practices to meet the recommended assigned noise affected level. Proponents should also inform all potentially impacted residents of the nature of works to be carried out, the expected noise levels and duration, as well as contact details
Outside recommended standard hours	Recommended assigned noise affected level: $RBL + 5 \text{ dB}$	A strong justification would typically be required for works outside the recommended standard hours. Proponents should apply all feasible and reasonable work practices to meet the noise affected level. Where all feasible and reasonable practices have been applied and noise is more than 5 dB(A) above the recommended assigned noise affected level, proponents should negotiate with the community

1. *RBL: Rating background level, L_{90} (dBA)*

Table 7 Recommended assigned noise levels for airborne noise at commercial and industrial premises

Land use	Management level dB(A) Leq(15min)
Industrial premises	75 dB (A)
Offices, retail outlets	70 dB (A)

3.5.3 Project construction noise criteria

The project-specific construction NMLs are detailed in Table 8 for residential receivers and Table 9 for non-residential receivers. The NMLs have been calculated based on the RBLs from NDY report.

Table 8 Residential construction NML

	Recommended standard hours NML L _{Aeq(15min)} dB	Outside of standard hours NML L _{Aeq(15min)} dB
All affected surrounding residential receivers	51	46

Table 9 Non-residential construction NMLs

Land use	Management level dB(A) Leq(15min)
Industrial premises	75 dB (A)
Offices, retail outlets	70 dB (A)

3.5.4 Construction noise impacts

At this stage a detailed construction methodology has not been established for the site. It is expected that the construction period would last for 18 months. Typical construction activities are expected on site which would be associated with standard commercial construction noise.

Once a detailed construction methodology is established it is recommended that a construction noise and vibration assessment is undertaken and a construction noise and vibration management plan established as required. The construction noise and vibration assessment would consider the expected construction activities and associated noise impacts together with recommended noise mitigation such as recommended methodologies, alternatives and any required scheduling.

It is expected that with typical construction noise mitigation and good work practices that the effects on the neighbouring properties from construction noise and vibration could be appropriately managed.

4 Equipment Schedules

4.1 Existing D1 Stage 1 noise emissions

The existing D1 Stage 1 site is located adjacent to the proposed D2 Stage 1 facility, however the two projects are considered to be separate and are located on separate lots. On this basis the two sites should be treated as separate developments and therefore cumulative noise for the two projects does not need to be considered. We highlight that the Project Amenity Noise Level criteria takes into consideration effects of cumulative noise from multiple nearby sites.

The noise impact assessment previously undertaken for D1 Stage 1 indicates that the predicted noise emissions to the nearby receivers is compliant with the applicable NT noise emission criteria.

4.2 Equipment Schedules

The D2 Stage 1 design includes the following key items of potentially noise generating equipment:

- Rooftop cooling towers
- OAP units
- Condensers
- Exhaust fans
- Roof top generator
- Load bank

Table 10 details the acoustic data utilised for the predictions based on the current mechanical and electrical specifications and design. The following operational scenarios have been assessed:

- Typical operation. Operational equipment includes: Cooling towers, OAP units, Exhaust fans, Condensers.
- Emergency testing. Operational equipment includes: Cooling towers, OAP units, Exhaust fan, one backup generator and one load bank, Condensers.

Should equipment selections change throughout the subsequent design stages, further acoustic review will be required to assess compliance with the applicable noise limits. Where equipment changes occur, additional acoustic mitigation may be required.

Table 10 D2 Stage1 Equipment Schedule

Source	Number of items	Sound Power Levels (dB)								Total SWL dB(A)
		Octave Band Frequency, Hz								
		63	125	250	500	1000	2000	4000	8000	
Cooling Tower ¹	6	75	75	70	64	65	66	58	51	71
Untreated Generator Exhaust ²	6	123	125	130	126	121	120	111	92	128
Untreated Generator engine surface noise ²		98	109	117	115	116	116	114	123	125
Client OAP unit ³	1	63	68	76	72	71	72	73	66	78
MCX OAP unit ⁴	2	64	70	71	70	67	68	67	60	74
Exhaust fan ⁵	1	89	83	86	84	83	81	76	70	88
Load bank ⁶	1	100	97	95	91	91	90	88	81	97
Condenser ⁷	9	61	68	70	64	59	59	56	55	67

1. Cooling tower selection is BAC S3E-1424-070/H.

2. Generator selection is MTU 16V4000 DS2500 G84F

3. Client OAP unit selection is Armcor XEP1200P3

4. MCX OAP unit selection is Armcor DHP900P3

5. Exhaust fan selection is Fantech APPM080CP12/25

6. Load bank is 2MW unit is containerised within acoustic enclosure to reach 76 dB(A) at 1m. Unit used for generator testing and emergency mode only

7. Condenser unit selection is Daikin RXM95WVMA. Noise spectrum is from empirical condenser and scaled to reach 67 dBA sound power level.

4.2.1 Generator mitigation package

An acoustic treatment package shall be installed to the rooftop containerised generators. The treatment package should be designed by the generator container supplier (Parratech or similar) to ensure a sound pressure level of 68 dBA at 1m is not exceeded.

Indicative treatment will include:

- Two engine exhaust silencers in series
- Acoustic sound absorbing treatment to the inside of the container
- Acoustic louvres + acoustic attenuator to the container ventilation intake
- Two acoustic attenuators to the container ventilation discharge.

The engineering report for the generator container shall be reviewed by the project acoustic consultant during subsequent design stages to assess compliance with the environmental noise emission requirements. This may necessitate additional noise modelling.

5 Noise modelling

5.1 Methodology

Preliminary noise modelling of the NEXTDC D2 Stage1 site has been undertaken for the site to predict potential noise impacts to neighbouring premises.

The prediction methodology utilised is the International Standard ISO 9613-2: 1996 *Acoustics – Attenuation of sound during propagation outdoors – Part 2: General Method of Calculation* implemented using SoundPLAN v9.0 acoustics software package.

5.2 Noise Modelling

Calculations of noise emissions during the Typical and Emergency testing scenarios have been undertaken using SoundPLAN v9.0.

A 7-storey building is proposed on-site, consisting of a basement level, a ground floor, data halls on Levels 2 to 6, and Level 7 serving as the roof. Generators are proposed to be located on the roof in individual pre-fabricated containers with provisions for intake, discharge and exhaust ventilation with acoustic treatment. Cooling towers are also proposed to be located on the roof.

OAP fans are proposed to be located on the ground floor, and exhaust fans will be installed near the ceiling of the basement level. A load bank used during generator testing only is proposed to be on the ground floor next to the water tanks.

A 3D image of the modelled data centre building and surrounds is shown in Figure 3.




Figure 3 3D model of data centre building and surrounds

5.3 Assumptions and limitations

The following assumptions and limitations apply to the assessment:

- In all scenarios, all equipment operates at 100% capacity continuously
- For the generator testing scenario, a single generator will be operated independently. As a worst case scenario this has been assumed to be the generator located closest to the receiver on the Harvey Street side.
- Load bank is running during Generator Testing scenario, and is located on ground floor next to water tanks.
- The equipment has been assumed to not emit any acoustic characteristics that would result in penalties. Further review of equipment manufacturer data may be required during subsequent design stages to ensure no tonal penalties are required to be added to the predicted noise levels.
- Basement-level mechanical exhaust fans will be designed with spatial allowances for acoustic treatment and attenuators to emit noise levels that are negligible compared to the noise emission levels experienced by receivers from other equipment.

The following acoustics issues are beyond the scope of this study and have not been addressed:

- Noise emission from office building as this is not part of this project and inadequate information is currently available.
- Noise emission from UPS System, Kiosk Transformer etc. which are assumed to be negligible
- Noise emission from other smaller plant equipment or fans associated with the D2 expansion which have not been specified at this stage. The noise contribution from smaller plant is assumed to be negligible and equipment is readily able to have noise mitigation implemented during subsequent design stages.
- Cumulative overall environmental noise impact from both D1 Stage 1 and D2 Stage 1 as the projects are on different sites.
- Environmental noise impact during construction phase.

5.4 Results

Noise emissions from the site have been predicted based on proposed building layout and current plant selections at the nearest receivers to the NEXTDC D2 Stage 1 site.

5.4.1 Typical operation

The results of the noise prediction for typical operation are summarised in Table 11.

Table 11 Typical Operation noise emission predictions

Receiver	Predicted noise level L_{Aeq} dB(A)	Project noise limit, L_{Aeq} dB(A)	Compliance?
Typical operation			
3 Harvey St	39	40	Y
12-16 Harvey St	38	40	Y

5.4.2 Generator testing

The results of the noise prediction for Generator testing scenario are summarised in Table 12.

Table 12 Generator Testing noise emission predictions

Receiver	Predicted noise level L _{Aeq} dB(A)	Project noise limit, L _{Aeq} dB(A)	Compliance?
Generator testing			
3 Harvey St	49	49	Y
12-16 Harvey St	47	49	Y

6 Conclusion

The project specific requirements for environmental noise emissions have been determined for the surrounding area around the proposed NEXTDC D2 Stage 1 site situated in Darwin City.


A 3D computational model of the site has been developed to predict noise emissions to the surrounding premises. The model has been based on the current detailed design selections and plant layouts.

Noise mitigation has been developed for the site, which includes acoustic treatment to the emergency Generator containers, site layouts and the selection of appropriately low noise equipment. The noise mitigation measures have been coordinated with the various other disciplines including Mechanical Engineering, Electrical Engineering and Architecture.

The assessment has shown that noise emissions are predicted to comply with the applicable noise limits at the nearest noise sensitive areas with the current design for both the Typical and Generator Testing scenarios.

Appendix A

Noise Contours



Noise level
dBLAeq




Signs and symbols

- Outdoor point source
- Residential Building
- Outdoor source
- D1 Existing Stage
- Substation
- NEXTDC D2 Stage 1 Building
- Residential building



REV	DATE	REVISION DETAILS	APPROVAL	SCALE	SIZE
1	28.01.25	DA	HM	NTS	A1
				DRAWN	CZ
				DESIGNED	CZ
				VERIFIED	HM
				APPROVER	HM
				DATE	28.01.25



REV	DATE	REVISION DETAILS
1	28.01.25	DA

APPROVAL	SCALE	SIZE
HM	NTS	A1
	DRAWN	CZ
	DESIGNED	CZ
	VERIFIED	HM

APPROVED	DATE
HM	28.01.25

PROJECT	TITLE	DRAWING No.	PROJECT No.	DATE	TYPE	DA	MA	DESCRIPTION
NEXTDC D2 Stages 1	SITE NOISE EMISSIONS GENERATOR TESTING SITUATION		P52571					

Document prepared by

Aurecon Australasia Pty Ltd

ABN 54 005 139 873

Aurecon Centre

Level 8, 850 Collins Street

Docklands, Melbourne VIC 3008

PO Box 23061

Docklands VIC 8012

Australia

T +61 3 9975 3000

F +61 3 9975 3444

E melbourne@aurecongroup.com

W aurecongroup.com



A better approach
to traffic solutions



NEXT DC, 2 and 6 Ryko Court, Darwin

Traffic Impact Assessment

Client // Hames Sharley (NT) Pty Ltd

Reference // 25T301

Date //30/01/2025

Next DC, 2 and 6 Ryko Court, Darwin- Traffic Impact Assessment

Document No: 25T301
Revision: A
Date: 30/01/25
Client Name: Hames Sharley (NT) Pty Ltd
Author: Afshin Beigi

SJ Traffic Consulting

ABN: 68 706 990 157
Mobile: 0451 501 408
Email: afshin@sjtrafficconsulting.com.au

COPYRIGHT: The Concepts and information contained in this document are the property of SJ Traffic Consulting. Use or copying of this document in whole or in part without the written permission of SJ Traffic Consulting constitutes an infringement of copyright.

DISCLAIMER: SJ Traffic Consulting has prepared this report in accordance with the instructions of the Client. It is prepared solely for their specific use. It is non-assignable and SJ Traffic Consulting accepts no liability for its use by a third party.

Document History

Revision	Date	Description	Prepared By
A	30/01/25	Traffic Impact Assessment– Next DC, 2 and 6 Ryco Court Darwin	Afshin Beigi

CONTENTS

1.0	INTRODUCTION	2
1.1	BACKGROUND.....	2
1.2	PROJECT SCOPE.....	2
2.0	EXISTING CONDITIONS	3
2.1	SUBJECT SITE.....	3
2.2	EXISTING ZONING	3
2.3	SURROUNDING ROAD NETWORK	3
2.4	PEDESTRIAN AND CYCLIST FACILITIES.....	4
2.5	PUBLIC TRANSPORT	5
2.6	TRAFFIC SURVEYS	5
3.0	PROPOSED DEVELOPEMENT.....	6
3.1	DEVELOPMENT PROPOSAL.....	6
4.0	PARKING ASSESSMENT	7
4.1	STATUTORY CAR PARKING REQUIREMENTS	7
4.2	BICYCLE END OF TRIP FACILITIES	8
4.3	LOADING BAYS.....	9
5.0	PARKING DESIGN REVIEW	10
5.1	CAR PARKING SPACE DIMENSION	10
5.2	MOTORCYCLE PARKING.....	10
5.3	PARKING FOR PEOPLE WITH DISABILITY.....	10
5.4	BICYCLE PARKING LAYOUT.....	10
6.0	LOADING AND WASTE COLLECTION ARRANGEMENTS .	11
6.1	LOADING AND WASTE COLLECTION	11
7.0	TRAFFIC IMPACT ASSESSMENT	14
7.1	TRAFFIC GENERATION.....	14
8.0	CONCLUSIONS AND RECOMMENDATIONS.....	15

1.0 INTRODUCTION

1.1 BACKGROUND

Hames Sharley (NT) Pty Ltd engaged SJ Traffic Consulting to prepare a traffic report to investigate the traffic impact of a proposed data centre at 2 and 6 Ryko Court, in Darwin City.

1.2 PROJECT SCOPE

This traffic report is intended to form part of a Development Application being prepared for submission to the Department of Infrastructure, Planning and Logistics (DIPL) and Darwin City Council and addresses the following issues:

- Assess the potential traffic impact of the proposed development on the surrounding road network
- The needs for all road users are accommodated in a safe and effective manner
- Proposed carpark layout and site access operates in a satisfactory manner and is designed in accordance with the standards

The report has been prepared in accordance with the Austroads document Guide to Traffic Management Part 12: Traffic Impacts of Developments (AGTM12).

In preparing this report, reference has been made to a number of background documents, including:

- Austroads, Guide to Traffic Management, Part 12: Traffic Impacts of Developments, 2009
- Austroads, Guide to Road Design, Part 4A: Unsignalised and Signalised Intersections, 2009
- Roads and Traffic Authority. Guide to Traffic Generating Developments, Sydney, 2002
- NT Planning Scheme, Department of Infrastructure, Planning and Logistics, July 2020
- Australian Standards. AS2890 Parking facility Series:
Part 1: Off-street car parking
Part 6: Off-street parking for people with disabilities


2.0 EXISTING CONDITIONS

2.1 SUBJECT SITE

The subject site is located at 2 and 6 Ryko Court (Lot 9704 and 9703) in Darwin City. The subject site is currently unoccupied.

The subject site and surrounding road network are illustrated in Figure 1 below.

Figure 1 – Subject Site



2.2 EXISTING ZONING

The site is currently zoned CB (Central Business) in the Northern Territory Planning Scheme (NTPS).

2.3 SURROUNDING ROAD NETWORK

Ryko Court is a Council managed road which runs north from Harvey Street and terminates into a court bowl. It has a 5.5 m wide undivided carriageway with a northeast to southwest alignment. Kerbside parallel parking is permitted along the road. The default urban speed limit of 50 km/h applies to the road.

Figure 2 – Ryko Court



Harvey Street is a Council managed road which runs in a north-west to south-east direction. It connects from Garramilla Boulevard to the south-east and continues as Day Street to the northwest. Harvey Street provides a 10.4 m wide carriageway, accommodating two way traffic flow. Kerbside parallel parking is provided on both sides of the road for the majority of its length. A default speed limit of 50 km/h applies to Harvey Street.

2.4 PEDESTRIAN AND CYCLIST FACILITIES

Off-road shared paths are provided on both sides of Garramilla Boulevard, within 100 m of the site, providing convenient access for pedestrian and cyclists to the site.

An off-road shared path is also provided on the western end of Harvey Street, approximately 300 m west of the site.

Figure 3 – Nearby cycling routes



Next to, 2 and 6 Ryko Court, Darwin
Traffic Impact Assessment

SJ Traffic Consulting

2.5 PUBLIC TRANSPORT


The closest bus stop to the site is located at the corner of Cavenagh Street and Garramilla Boulevard, approximately 550 m walking distance to the site.

Routes accessible from this stop include services linking to the Palmerston and Casuarina bus interchanges which provide access to further local services.

2.6 TRAFFIC SURVEYS

A traffic survey was undertaken at the intersection of Harvey Street and Garramilla Boulevard on 12 December 2024 between 7 am to 9 am and 3 pm to 6 pm. The peak hour traffic volumes are summarised in Figure 4 below.

Figure 4 – Peak hour traffic volumes



3.0 PROPOSED DEVELOPEMENT

3.1 DEVELOPMENT PROPOSAL

The proposal is to construct a five storey data centre with a lower ground level car park. The proposed facility will comprise of office areas on the ground floor, with switch rooms, data halls and services on the above ground levels.

We have been advised that the facility will operate 24 hours, 7 days a week, with up to 70 people at any one time, comprising of 40 staff and 30 customers.

The development will provide 12 x 90-degree angled car parking spaces on the lower ground floor (including one accessible space). Six motorcycle parking spaces and 27 bicycle parking spaces have also been provided.

A copy of the proposed development plans is included in Appendix A.

4.0 PARKING ASSESSMENT

4.1 STATUTORY CAR PARKING REQUIREMENTS

Statutory requirements for provision of car parking are set out in Clause 5.2.4.1 of Northern Territory Planning Scheme. The various components of the proposed development have been assessed based on the following:

- ground level office, including meeting rooms and breakout areas: office
- ancillary storage areas: warehouse
- data hall: the planning scheme does not provide car parking rates for a data centre. However, it is expected this area will not generate parking demand, and is treated as ancillary to the office component for this assessment.

On this basis, the parking requirements for the development is set out in Table 1 below.

Table 1: Parking requirements

Land use	Area m2	Parking rate	Parking requirement
Office	1,154	2 for every 100m2 of net floor area	23 spaces
Warehouse	309	1 for every 100m2 of net floor area	3 spaces
Total			26 spaces

The development has a statutory requirement of 26 spaces. The provision of 12 spaces on site therefore results in a parking shortfall of **14 spaces**.

Clause 5.9.1.12 outlines considerations that can be applied to reduce the number of car parking spaces required, subject to the consent authority.

Table 2 below summarises the reductions that can be applied to the car parking requirements.

Table 2: Reduction in car parking spaces – Clause 5.9.2.12

Category	Description	Assessment	Parking Reduction
Motorcycle parking	Reduction of 1 car parking space for every 3 motorcycle parking spaces proposed, but only to a maximum of 1 motorcycle parking space for every 25 (or more) car parking spaces required by Clause 5.9.2.11	6 motorcycle parking spaces have been provided.	1 space
Bicycle parking	For any bicycle parking spaces proposed in excess of those required by the table to clause 5.3.7, a reduction of 1 car parking space for every 10 excess bicycle parking space	An excess of 23 bicycle parking spaces have been provided on site.	2 spaces

Access to alternative transport options	The development is located within 200 m of a dedicated off-road bicycle path or on-road bicycle lane	Off-road bicycle paths are provided along Garramilla Boulevard, which is located within 200 m of the site.	5 % (1 space)
Total parking reduction			4 spaces
Reduced parking requirement			22 spaces

Applying the above reductions, the reduced parking requirement is 22 spaces. The provision of 12 on-site parking spaces will therefore incur a shortfall of **10 spaces**.

4.2 BICYCLE END OF TRIP FACILITIES

Clause 5.3.7 of the NTPS specifies the requirements for end of trip facilities for new developments in Zones HR, CB, C, SC and TC. The development is located within a CB (Central Business) zone.

Table 5.3.7 outlines the minimum number of bicycle parking spaces and showers required. The various components of the proposed development have been assessed based on the following:

Component	Adopted use	Minimum number of bicycle parking spaces	Minimum number of showers
ground level office, including meeting rooms and breakout areas	Office	1 space per 300m ² net floor area	1 shower for up to 1500m ² net floor area, plus 1 additional shower for up to every 1500m ² thereafter.
ancillary storage areas	Non residential building	1 space per 300m ² net floor area	1 shower for up to 50 staff, plus 1 additional shower for up to every 50 staff thereafter.

- data hall: the planning scheme does not provide bicycle parking rates for a data centre. However, it is expected this area will not generate bicycle parking demand, and is treated as ancillary to the office component for this assessment.

Table 3: End of Trip Facilities requirements Table 5.3.7 of NTPS

Land use	Area m ²	Minimum number of bicycle parking spaces	Minimum number of showers
Office	1,157	4	1
Non residential building	309	1	1 (based on expected 40 staff)

Total		5 spaces	2 showers
--------------	--	-----------------	------------------

Based on this, the proposed data centre will have a requirement of:

- 5 bicycle parking spaces
- 2 showers

27 bicycle parking spaces have been provided within the car park, within a secured storage area. This provision is well in excess of the NTPS requirements, with an excess of 22 bicycle parking spaces.

Two showers have also been provided within the ground level, satisfying the requirement.

4.3 LOADING BAYS

Clause 5.2.5 to Part 5 of the NPTS outlines the loading bay requirements for new developments.

The minimum number of loading bays is specified under Table to Clause 5.2.5.

The various components of the proposed development have been assessed based on the following land uses:

- ground level office, including meeting rooms and breakout areas: office
- data centre: warehouse

Table 4: Loading requirements Table 5.2.5 of NTPS

Land use	Area m2	Minimum number of loading bays	Loading bay requirement
Office	1,154	1 loading bay for every 2000m2 of the total net floor area, or part thereof	1
Data centre (Warehouse)	5,908	1 loading bay for a single occupation of a net floor area of 10 000m2 or less; and 1 loading bay for every 5000m2 of net floor area or part thereof in excess of 10 000m2	1

Based on the above assessment, there is a requirement for 2 loading bays. However, as the facility will operate as a single occupancy, it is appropriate that a variation be sought to provide one loading bay for the proposed development.

A loading bay measuring 8.8 m x 2.5 m has been provided within the lower ground floor car park, satisfying the requirements of Clause 5.2.5.

5.0 PARKING DESIGN REVIEW

5.1 CAR PARKING SPACE DIMENSION

It is proposed to provide 12 x 90-degree angled car parking spaces (include one accessible space) within the lower ground floor car park. The proposed parking spaces have been provided at 2.5 m width and 5.5 m length, accessed via an aisle width of 6.6m, in accordance with Clause 5.2.4.4 of the Northern Territory Planning Scheme.

5.2 MOTORCYCLE PARKING

Six motorcycle parking spaces have been proposed within the lower ground floor car park. These have been provided with a width of 1.2 m and length of 2.5 m, in accordance with AS 2890.1-2004.

5.3 PARKING FOR PEOPLE WITH DISABILITY

One accessible space will be provided onsite. The proposed accessible space and adjacent shared area have been provided at a width of 2.5m and length of 5.5m, in accordance with AS2890.6:2009.

5.4 BICYCLE PARKING LAYOUT

27 bicycle parking spaces have been provided within the car park, within a secured storage area. The bicycle parking is provided in a combination of vertical wall racks and horizontal hoops, comprising of:

- 21 wall mounted racks, provided at 1.2m long and 500 mm wide, in accordance with AS 2890.3
- 6 horizontal bicycle hoops, provided at 1.8m long and 500 mm wide, in accordance with AS 2890.3.

The bicycle parking area is provided in a convenient location, easily accessible by staff.

6.0 LOADING AND WASTE COLLECTION ARRANGEMENTS


6.1 LOADING AND WASTE COLLECTION


Loading will occur within the lower ground level car park. The loading vehicle will access the site, reverse into the loading bay, and exit via the eastern exit point. Goods will be trolleyed between the loading bay and the delivery vehicle. Deliveries to the site is expected to be infrequent, undertaken with vehicles up to 8.8 m in length, and with arrivals managed by staff outside of business operating times.

A bin storage area will be provided on the north-eastern corner of the ground level car park. Waste collection will occur on site and will be undertaken by a 10.1m long waste collection vehicle. It is anticipated the 10.1 m long waste collection vehicle will be the largest vehicle servicing the proposed development.

A swept path assessment demonstrating the 10.1 m vehicle accessing the loading zone is shown below in **Error! Reference source not found.** to 7.

Figure 6 – Waste collection vehicle swept path





7.0 TRAFFIC IMPACT ASSESSMENT

7.1 TRAFFIC GENERATION

The NSW Roads and Maritime Services (RMS) (formerly Roads and Traffic Authority (RTA)) “Guide to Traffic Generating Developments” (the RTA Guide) provides trip generation rates for a variety of land uses. The RTA Guide does not provide trip generation rates for data centres. Therefore, the traffic generated by the development was determined empirically.

The following has been assumed:

- It is estimated there will be up to 40 staff on site at any one time
- Staff will all arrive within the AM peak hour and depart in the PM peak hour
- With the provision of bicycle parking and off-road shared paths in close proximity of the site, it is expected that a proportion of staff will cycle to work. For the purposes of this assessment, an estimation of 20 % of staff will cycle or walk to work
- No customers will arrive or depart the site during the AM and PM peak hours.

Based on this assumption, the development will generate 32 vehicle trips in the AM and PM peak periods.

It is anticipated that all vehicle movements will be arriving / departing to/from Garramilla Boulevard and Harvey Street.

The traffic generation of 32 trips per hour is minimal and will not impact the capacity of the surrounding road network and the level of service of the intersections in the area.

As such, there are no improvements required to the surrounding road network to accommodate for the additional traffic generated by the development.

8.0 CONCLUSIONS AND RECOMMENDATIONS

Based on the analysis and discussions presented within this report, the following conclusions are drawn:

- 12 parking spaces will be provided on site. This represents a shortfall of **10 parking spaces**
- One loading bay has been provided within the lower ground floor car park
- The car park has been designed in accordance with AS 2890.1 and AS 2890.6
- Bicycle parking provision is in excess of the requirements, and have been designed in accordance with AS 2890.3
- Loading and waste collection will occur on-site within the carpark. The vehicle can enter and exit the carpark in a forwards direction.
- The development will generate up to 32 vehicle trips in the peak hours. This is negligible and will have minimum impacts to the surrounding road network. The anticipated traffic generation will not require improvements or upgrades to the surrounding road network.

APPENDIX A

Development Plans

NORTHERN TERRITORY OF AUSTRALIA

Planning Act 1999 - sections 54 and 55

DEVELOPMENT PERMIT

DP23/0213

DESCRIPTION OF LAND THE SUBJECT OF THE PERMIT

Lot 09702
Town of Darwin
8 RYKO CT, DARWIN CITY

APPROVED PURPOSE

To use and develop the land for the purpose of a Data Centre, in accordance with the attached schedule of conditions and the endorsed plans.

VARIATIONS GRANTED

Clauses 5.2.4.4 (Layout of Car Parking Areas), 5.2.5 (Loading Bays), 5.5.15 (Design in Commercial and Mixed Use Areas) and 5.5.16 (Active Street Frontage) of the Northern Territory Planning Scheme 2020.

BASE PERIOD OF THE PERMIT

Subject to the provisions of sections 58, 59 and 59A of the *Planning Act 1999*, this permit will lapse two years from the date of issue.

 Digitally signed
by Adelle
Godfrey
Date: 2023.09.01
13:31:22 +09'30'

ADELLE GODFREY
Delegate
Development Consent Authority
1 September 2023

DEVELOPMENT PERMIT

DP23/0213

SCHEDULE OF CONDITIONS

CONDITIONS PRECEDENT

1. Prior to the endorsement of plans and prior to commencement of works, amended plans to the satisfaction of the consent authority must be submitted to and approved by the consent authority. When approved, the plans will be endorsed and will then form part of the permit. The plans must be drawn to scale with dimensions and must be generally in accordance with the plans submitted with the application but modified to show:
 - Additional landscaping that achieves compliance with Clause 5.2.6.2 (Landscaping in Zone CB) of the NT Planning Scheme 2020.
2. Prior to the endorsement of plans and prior to commencement of works, a landscape plan to the satisfaction of the consent authority must be submitted to and approved by the consent authority. When approved, the plan will be endorsed and will then form part of the permit. The plan must be drawn to scale with dimensions. The landscaping plan must be generally in accordance with the landscape concept plan dated (May 2023) prepared by TCL and incorporate additional landscaping required under condition 1 of this permit. The plan must include a planting schedule of all proposed trees, shrubs and ground covers, including botanical names, common names, pot sizes, sizes at maturity, and quantities of each plant. All species selected must be to the satisfaction of the consent authority.
3. Prior to the commencement of works (including site preparation), an engineered plan completed by a suitably qualified civil engineer demonstrating the on site collection of stormwater and its discharge into the local underground stormwater drainage system, shall be submitted to, and approved by the City of Darwin, to the satisfaction of the consent authority. The plan shall include details of site levels, and Council's stormwater drain connection point/s and connection details.
4. Prior to the commencement of works, a traffic impact assessment report is to be prepared by a suitably qualified traffic engineer in accordance with the Austroads Document Guide to Traffic Management Part 12: Traffic Impacts of Developments, in the report structure provided as Appendix C of that document, with particular attention to vehicular, pedestrian, cyclist and public transport issues and opportunities. The Traffic Impact Assessment report is to also include swept paths for waste collection vehicles entering and exiting the site and identifying any necessary upgrades to the surrounding street network to the requirements of the City of Darwin, to the satisfaction of the consent authority.
5. Prior to the commencement of works (including site preparation), in principle approval is required for the crossover and driveway to the site from the City of Darwin road reserve, to the satisfaction of the consent authority.
6. Prior to the commencement of works (including site preparation), the applicant is to prepare a dilapidation report covering infrastructure within the road reserve to the requirements of the City of Darwin, to the satisfaction of the consent authority.

7. Prior to the commencement of works (including site preparation), a Waste Management Plan demonstrating waste disposal, storage and removal in accordance with City of Darwin's Waste Management Guidelines, shall be submitted to and approved by the City of Darwin, to the satisfaction of the consent authority.
8. Prior to the commencement of works (including site preparation), the applicant is to prepare a Site Construction Management Plan (SCMP) to the requirements of the City of Darwin, to the satisfaction of the consent authority. The SCMP should specifically address the impact to Council owned public spaces and include a waste management plan for disposal of waste to Shoal Bay, traffic control for affected City of Darwin roads, haulage routes, storm water drainage & sediment control, use of City of Darwin land, and how this land will be managed during the construction phase.

GENERAL CONDITIONS

9. The works carried out under this permit shall be in accordance with the drawings endorsed as forming part of this permit.
10. The owner of the land must enter into agreements with the relevant authorities for the provision of water supply, sewerage, electricity and telecommunication networks to the development shown on the endorsed plan in accordance with the authorities' requirements and relevant legislation at the time.

Please refer to notations 2, 3 and 4 for further information.
11. Any developments on or adjacent to any easements on site shall be carried out to the requirements of the relevant service authority to the satisfaction of the consent authority.
12. Stormwater is to be collected and discharged into the drainage network to the technical standards of and at no cost to the City of Darwin, to the satisfaction of the consent authority.
13. All works recommended by the traffic impact assessment are to be completed to the requirements of the City of Darwin, to the satisfaction of the consent authority.
14. The kerb crossovers and driveways to the site approved by this permit are to meet the technical standards of City of Darwin, to the satisfaction of the consent authority.
15. No fence, hedge, tree or other obstruction exceeding a height of 0.6m is to be planted or erected so that it would obscure sight lines at the junction of the driveway and the public street to the requirements of the City of Darwin, to the satisfaction of the consent authority.
16. Storage for waste disposal bins is to be provided to the requirements of the City of Darwin, to the satisfaction of the consent authority.
17. Upon completion of any works within or impacting upon existing road reserves, the infrastructure within the road reserve shall be rehabilitated to the standards and requirements of the City of Darwin and returned to the condition as documented in the dilapidation report.
18. Before the use or occupation of the development starts, the areas set aside for the parking of vehicles and access lanes as shown on the endorsed plans must be:
 - a. constructed;

- b. properly formed to such levels that they can be used in accordance with the plans;
- c. surfaced with an all weather seal coat;
- d. drained;
- e. line marked to indicate each car space and all access lanes; and
- f. clearly marked to show the direction of traffic along access lanes and driveways to the satisfaction of the consent authority.

Car parking spaces, access lanes and driveways must be kept available for these purposes at all times.

19. The loading and unloading of goods from vehicles must only be carried out on the land and within the designated loading bays, to the satisfaction of the consent authority.
20. All substation, fire booster and water meter arrangements are to be appropriately screened to the requirements of Power and Water Corporation and NT Fire and Emergency Services, to the satisfaction of the consent authority. Any screening should soften the visual impact of such infrastructure and details will need to be resolved in consultation with the Power and Water Corporation, and NT Fire and Emergency Services.
21. All air conditioning condensers (including any condenser units required to be added or replaced in the future) are to be appropriately screened from public view, located so as to minimise thermal and acoustic impacts on neighbouring properties and condensate disposed of to ground level in a controlled manner to the satisfaction of the consent authority.
22. All pipes, fixtures, fittings and vents servicing any building on the site must be concealed in service ducts or otherwise hidden from view to the satisfaction of the consent authority.
23. The development must be designed and constructed to comply with the acoustic treatment recommendations of the Acoustics Spatial Co Ordination Report, dated 28 June 2023, prepared by Norman Disney and Young, and a statement from a suitably qualified acoustic engineer confirming compliance with Acoustics Report must be submitted prior to occupation of the development, to the satisfaction of the consent authority.
24. Before the use/occupation of the development starts, the landscaping works shown on the endorsed plans must be carried out and completed to the satisfaction of the consent authority.
25. The landscaping shown on the endorsed plans must be maintained to the satisfaction of the consent authority, including that any dead, diseased or damaged plants are to be replaced.

NOTES

1. The Authority advises the applicant that the building and façade must be constructed in accordance with the materials shown on Drawings numbered DA400(N) and DA401(L), dated 29/06/2023, prepared by Hames Sharley and the drawings endorsed through this permit.
2. The Power and Water Corporation advises that the Water and Sewer Services Development Section (waterdevelopment@powerwater.com.au) and Power Network Engineering Section (powerdevelopment@powerwater.com.au) should be contacted via email a minimum of 1 month prior to construction works commencing in order to determine the Corporation's servicing requirements, and the need for upgrading of on site and/or surrounding infrastructure.

3. All developers, including owner builders, are required to comply with Commonwealth telecommunications requirements. Under Commonwealth law, developers are generally required to provide fibre ready pit and pipe in their developments at their expense. Developers may be able to access an exemption from these arrangements in some circumstances. For more information visit www.infrastructure.gov.au/tind
4. If you choose nbn to service your development, you will need to enter into a development agreement with nbn. The first step is to register the development via <http://www.nbnco.com.au/develop> or <http://www.nbnco.com.au/plan> with the [nbn/new developments.html](http://www.nbnco.com.au/newdevelopments.html) once registered nbn will be in contact to discuss the specific requirements for the development. Nbn requires you to apply at least 3 months before any civil works commence. All telecommunications infrastructure should be built to nbn guidelines found at <http://www.nbnco.com.au/develop> or <http://www.nbnco.com.au/plan> with the [nbn/newdevelopments/builders designers.html](http://www.nbnco.com.au/newdevelopments/buildersdesigners.html)
5. Transport and Civil Services Division, Department of Infrastructure, Planning and Logistics advises that surface stormwater run off from the development site onto the Garramilla Boulevard Road reserve is not permitted.
6. Any proposed works on/over City of Darwin property shall be subject to separate application to City of Darwin and shall be carried out to the requirements and satisfaction of City of Darwin.
7. Designs and specifications for landscaping of the road verges adjacent to the property shall be submitted for approval by City of Darwin and all approved works shall be constructed at the applicant's expense, to the requirements of City of Darwin.
8. Notwithstanding the approved plans, any proposed signage for the site shall be subject to a separate assessment in accordance with City of Darwin Policy Number 42 – Outdoor Advertising Signs Code.
9. This development permit is not an approval to undertake building work. You are advised to contact a Northern Territory registered building certifier to seek a building permit as required by the *Northern Territory Building Act 1993* before commencing any demolition or construction works.
10. Any proposed works which fall within the scope of the *Construction Industry Long Service Leave and Benefits Act 2005* must be notified to NT Build by lodgement of the required Project Notification Form. Payment of any levy must be made prior to the commencement of any construction activity. NT Build should be contacted via email (info@ntbuild.com.au) or by phone on 08 89364070 to determine if the proposed works are subject to the Act.

This document contains drawing numbers:

2023/0228/01 to 2023/0228/19

Referred to in Permit No: DP23/0213

Issued by the consent authority on: 01 September 2023

All drawings contained within this document have been authorised by the delegate of the consent authority.


Digitally signed
by Amit Magotra
Date: 2023.10.06
13:49:43 +0930

Delegate

Drawing number 2023/0228/01

Referred to in Permit No: DP23/0213

SOFT LANDSCAPE AREA		
Family	Type	Area
Floor	Landscaping - Planters	5.9 m²
Floor	Landscaping - Short Grass	25.6 m²
Floor	Landscaping - Planters	24.2 m²
Floor	Landscaping - Planters	20.3 m²
Floor	Landscaping - Grass	8.5 m²
Floor	Landscaping - Planters	6.5 m²
Floor	Landscaping - Planters	15.2 m²
Floor	Landscaping - Grass	2.6 m²
Floor	Landscaping - Swale Planting	27.3 m²
Floor	Landscaping - Planters	3.1 m²
Floor	Landscaping - Planters	2.0 m²
		140.0 m²



DATE	REVISION HISTORY	DRAWN BY	CHK BY
20/09/2023	E TECHNICAL DESIGN - FINAL		
14/09/2023	D DESIGN DEVELOPMENT		
20/09/2023	C TECHNICAL DESIGN - DRAFT		
20/09/2023	B DESIGN DEVELOPMENT		
20/09/2023	A PRELIMINARY DESIGN CLAYOUT		

NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
4. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS
Architect HAMES SHARLEY
Services NDY
Structural PITCHARD FRANCES

PRINCIPAL CONTRACTOR

CLIENT



NEXTDC
GPO Box 3219
Brisbane QLD 4001
T +61 7 3177 4777

[Contractor / Consultant / Document Author]
Hames Sharley

Document Author Project Number

Key Plan

Site Stage NEXTDC Project Number
D1 S1 D1.001

Project Address
2 HARVEY STREET,
DARWIN, 0800, NT

Project Name
NEXTDC D1 - LOT 9702

Drawing Title
EXTERNAL WORKS -
OVERALL

Drawing Status
TECHNICAL DESIGN -
DRAFT

DRAWN	HEB	DATE	20/09/2023
CHECKED	HEB	DATE	20/09/2023
APPROVED	HEB	DATE	20/09/2023

Scale	Sheet	File Name
1 : 100	A1	

Day	Rev
D1-AR-01-0010	E

13/09/2023 14:23:28 AM

LEGEND	
	MATERIAL / ITEM - REFER LEGEND
	FINISH - REFER SCHEDULES
MATERIAL / ITEM SCHEDULE	
TAG	DESCRIPTION
BAL003	BALUSTRADE TYPE 3
BOL003	REMOVABLE BOLLARDS (PROPRIETARY ITEM SELECTION)
BPR003	WHEELSTOP - REMOVABLE
PAV003	CARPARK & DRIVEWAY
RA0005	ROOF ACCESS LADDER
TAC002	RUBBER TACTILE INDICATORS

NO.	REVISION HISTORY	DATE	CHK	APP
01	TECHNICAL DESIGN - FINAL			
02	TECHNICAL DESIGN - PRELIMINARY			
03	TECHNICAL DESIGN - PRELIMINARY			
04	TECHNICAL DESIGN - PRELIMINARY			

NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
4. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS
Architect HAMES SHARLEY
Services NDT
Structural PITCHARD FRANCES

PRINCIPAL CONTRACTOR

CLIENT



NEXTDC
GPO Box 3219
Brisbane QLD 4001
T +61 7 3177 4777

[Contractor / Consultant / Document Author]

Hames Sharley

Document Author Project Number

Key Plan

Site	Stage	NEXTDC Project Number
D1	S1	D1.001

Project Address
2 HARVEY STREET,
DARWIN, 0800, NT

Project Name
NEXTDC D1 - LOT 9702

Drawing Title
EXTERNAL WORKS -
SHEET 2



Drawing Status
TECHNICAL DESIGN -
DRAFT

Drawn	Check	Rev
HS	HS	08/09/2023
HS	HS	08/09/2023
HS	HS	08/09/2023

Scale	Sheet	File Name
1 : 50	A1	


D1-AR-01-0012

13/09/2023 14:28:46



BIN STORE - 3D VIEW

Drawing number 2023/0228/04
Referred to in Permit No: DP23/0213



1 EXTERNAL WORKS
1:50

LEGEND

CW150 MATERIAL / ITEM - REFER LEGEND
CINT001 SELECTED FINISH - REFER SCHEDULES

MATERIAL / ITEM SCHEDULE

TAG DESCRIPTION
BAL001 BALUSTRADE TYPE 4
RAC003 MESH GRATING (PLATFORMS ETC)
TAC002 RUBBER TACTILE INDICATORS

DATE	REV	REVISION HISTORY	DRAWN	CHECKED	QA
08/09/2023	1	TECHNICAL DESIGN - FINAL			
08/09/2023	2	TECHNICAL DESIGN - DRAFT			
08/09/2023	3	TECHNICAL DESIGN - DRAFT			
08/09/2023	4	TECHNICAL DESIGN - DRAFT			

NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
4. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS
Architect HAMES SHARLEY
Services NDY
Structural PRITCHARD FRANCES

PRINCIPAL CONTRACTOR

CLIENT



NEXTDC
GPO Box 3219
Brisbane QLD 4001
T: +61 7 3177 4777

[Contractor / Consultant / Document Author]

Hames Sharley

Document Author Project Number

Key Plan

Site	Stage	NEXTDC Project Number
D1	S1	D1.001

Project Address
2 HARVEY STREET,
DARWIN, 0800, NT

Project Name
NEXTDC D1 - LOT 9702

Drawing Title
EXTERNAL WORKS -
SHEET 3


Drawing Status
TECHNICAL DESIGN -
DRAFT

Drawn	Check	Rev
HD	HD	08/09/2023
HD	HD	08/09/2023
HD	HD	08/09/2023

Scale	Sheet	File Name
1:50	A1	
Day 01		Rev

D1-AR-01-0013 C

13/09/2023 9:57:24 AM



ACOUSTIC LEGEND	
	Rw 45
	Rw 55
	Rw 60

NOTE
TO BE READ TO CONJUNCTION WITH NEXTDC
MEETING ROOM STANDARDS/CONSTRUCTION GUIDELINES
& WALL TYPE SCHEDULES.

NO.	REVISION HISTORY	DATE	DRN	CHK	QA
01/000001	0 TECHNICAL DESIGN - FINAL				
01/000002	01 TECHNICAL DESIGN - DRAFT				
01/000003	02 TECHNICAL DESIGN - DRAFT				
01/000004	03 TECHNICAL DESIGN - DRAFT				
01/000005	04 DRAFT FILE				

NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CONFIRM ALL MEASUREMENTS ON SITE
4. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
5. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS
Architect HAMES SHARLEY
Services NDY
Structural PITCHARD FRANCES
PRINCIPAL CONTRACTOR

CLIENT

NEXTDC
GPO Box 3219
Brisbane QLD 4001
T +61 7 3177 4777

[Contractor / Consultant / Document Author]
Hames Sharley


Document Author Project Number
Key Plan

Site	Stage	NEXTDC Project Number
D1	S1	D1.001

Project Address
2 HARVEY STREET,
DARWIN, 0800, NT

Project Name
NEXTDC D1 - LOT 9702
Drawing Title
ACOUSTIC DIAGRAMS -
GROUND FLOOR

Drawing Status		TECHNICAL DESIGN - DRAFT	
DRAWN	HB	DATE	08/09/2023
CHECKED	HB	DATE	08/09/2023
APPROVED	HB	DATE	08/09/2023
Scale	Sheet	File Name	Rev
1 : 100	A1		
D1-AR-01-0050			D



CMT50 ← MATERIAL (ITEM-BEER LEGEND)

QUESTION

MATERIAL / TEM SCHEDULE

TAG	DESCRIPTION
CARG01	CARPET TILES - TYPE 1- FOSSIL
CF7002	300X300 FLOOR TILE - P4 FINISH
MATG01	MATTWELL
RES001	SHEET VINYL - FLOOR
RES002	SHEET VINYL - FLOOR
RES003	VINYL SKIRTING

30.08.2023	C	TECHNICAL DESIGN - FINAL ISSUE			
30.08.2023	B	TECHNICAL DESIGN - DRAFT ISSUE UPDATE			
21.07.2023	A	TECHNICAL DESIGN - DRAFT ISSUE			
DATE	No.	REVISION HISTORY	DRW	CHK	QA

NOTE:

1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CONFIRM ALL MEASUREMENTS ON SITE
4. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
5. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS

Architect HAMES SHARLEY

Services	NOY
----------	-----

Structural PRITCHARD FRANCIS

CUEN



NEXT DC

NEXTDC
GPO Box 3219
Brisbane QLD 4001
T: +61 7 3177 4777

[Contractor / Consultant / Document Author]

James
SHARLEY

Document Author Project Number

Key Plans



Site	Stage	NEXTDC Project Number
D1	S1	D1.001

Project Address
2 HARVEY STREET,
DARWIN, 0800, NT

Project Name
NEXTDC D1 - LOT 9702


Drawing Title
FLOOR PLAN - GROUND

Drawing Status
TECHNICAL DESIGN -
DRAFT

DRAWN HS	Date 08/09/2023
CHECKED HS	Date 08/09/2023
APPROVED HS	Date 08/09/2023

Scale	Sheet	File Name
1 : 100	A1	

D1-AR-01-3000



- 1 THE CONTRACTOR IS SOLELY RESPONSIBLE FOR THE WATER-TIGHTNESS OF THE STRUCTURAL INTEGRITY OF THE ROOF
- 2 ENSURE ROOF SYSTEMS INCLUDING JOISTS, DOWNSPIPS AND FLASHINGS ARE WITHOUT DEFECT OR WATER LEAKS, AND THAT THE ROOF IS LEAK FREE TO THE SATISFACTION OF THE CLIENT AT ALL TIMES (EVEN PRECAUTION TO BE TAKEN TO PREVENT DAMAGE TO THE ROOF DURING REMOVAL OF MATERIALS AND ALL DEBRIS MUST BE REMOVED FROM THE ROOF AND REMOVED TO THE LANDSIDE WITHIN 11 WEEKS OF BEING REMOVED)
- 3 DOWNPIPES AND ESCAPE FROM ROOF LEVELS MUST BE PROVIDED WITH A CONDUIT TO THE GROUND
- 4 ACCESS ARE TO BE FULLY HYDRAULICALLY SEALED BETWEEN RAFTERS/WATER AND BELOWGROUND DRAIN
- 5 PROVIDE EXPANDED JOISTS TO BOX JOISTS AS REQUIRED TO MEET REGULATORY STANDARDS
- 6 ROOF JOISTS TO BE INSTALLED IN ACCORDANCE WITH AS 1593-1990 AND AS/NZS 2962
- 7 REFER TO MECHANICAL DRAWINGS FOR DETAIL OF AIR-LOCKING JOIST CONNECTIONS
- 8 ALL ROOFJOISTS TO BE INSTALLED IN STRICT ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS
- 9 AC PLANT PLATFORMS TO BE NOT GIVEN DRAINAGE, SIZES PLANT PLATFORMS TO BE APPROVED BY THE APPROVAL OF THE STRUCTURAL ENGINEER
- 10 PROVIDE MECHANICAL DRAWINGS FOR DETAIL OF AIR-LOCKING JOIST CONNECTIONS, THE CONTRACTOR MUST CONFIRM THAT ALL MECHANICAL PLATFORMS ARE SITED TO PREVENT OR REDUCE AIR LEAKS
- 11 PROVIDE DETXITE FLATFLOP OR SIMILAR APPROVED AROUND SITE PERIMETER TO DISBURSE WATER TEST SEAL AROUND PENETRATIONS
- 12 DRAINAGES BETWEEN 45 AND 90 DEGREES WILL NOT BE ACCEPTED
- 13 ANY HEIGHT OVER 300MM REQUIRES A LADDER, THE LADDER MUST BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF AS/NZS 4576 AND THE LADDER MUST BE APPROVED BY THE STRUCTURAL ENGINEER
- 14 ANY PLATFORM HEIGHT GREATER THAN 1000MM MUST HAVE HANDRAILS/AUSTRAL TO ALL SIDES

- Roof access walkway**
- 1 FINAL LOCATION OF WALKWAY TO BE COORDINATED WITH MECHANICAL DUCTS AND ALL OTHER EQUIPMENT ON THE ROOF
 - 2 SPACER BETWEEN CESSILAR METALS TO BE USED TO FIT SUPPORT SECTIONS
 - 3 WALKWAY SHOULD AT ALL TIMES BE INSTALLED 2M AWAY FROM ANY FALL ZONE
 - 4 WHERE DISTANCE IS BELOW 2M HANDRAILS SHALL BE INSTALLED
-
- LEGEND**
- CW750 ← MATERIAL / ITEM - REFER LEGEND
- INTG0301 ← SELECTED FINISH - REFER SCHEDULES

MATERIAL / ITEM SCHEDULE	
TAG	DESCRIPTION
RA5001	ROOF ACCESS WALKWAY
RA5002	METAL BALUSTRADING
RA5004	ROOF ACCESS STEPS & HANDRAIL
RPM001	COLORBOND PROFILED METALDECK ROOFING

[Contractor / Consultant / Document Author]

James Sharley

Document Author Project Number

Key Plan



Site	Stage	NEXTDC Project Number
D1	S1	D1.001

Project Address
2 HARVEY STREET,
DARWIN, 0800, NT



Project Name	NEXTDC D1 - LOT 9702
--------------	----------------------

Drawing Title
ROOF PLAN

Drawing Status
TECHNICAL DESIGN -
DRAFT

DRAWN HS	Date 08/09/2023
CHECKED HS	Date 08/09/2023
APPROVED HS	Date 08/09/2023

Scale 1 : 100	Sheet A1	File Name
Dwg no:		Rev
D1-AR-01-3010		C



DESIGNED BY	TECHNICAL DESIGNER - PLAN
DRAWN BY	ROBERT
CHECKED BY	TECHNICAL DESIGNER - SHAFT
APPROVED BY	TECHNICAL DESIGNER - SHAFT

DATE 08/09/2023 REVIEW HISTORY DRAFT DKS DKA

- NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
 2. DO NOT SCALE FROM DRAWINGS
 3. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
 4. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS

Architect HAMES SHARLEY

Services NDY

Structural PITCHARD FRANCES

PRINCIPAL CONTRACTOR



[Contractor / Consultant / Document Author]

Hames Sharley

Document Author Project Number

Key Plan

Site	Stage	NEXTDC Project Number
D1	S1	D1.001

Project Address

2 HARVEY STREET,
DARWIN, 0800, NT


Project Name

NEXTDC D1 - LOT 9702


Drawing Title

SECTIONS

Drawing Status			
TECHNICAL DESIGN - DRAFT			
DRAWN	HEB	DATE	08/09/2023
CHECKED	HEB	DATE	08/09/2023
APPROVED	HEB	DATE	08/09/2023
Scale	Sheet	File Name	
1 : 100	A1		
Day 01			Rev
D1-AR-01-6000			C



1 SECTION
0061 1 : 100



2 SECTION
3000 1 : 100


DESIGNED	TECHNICAL DESIGN - FINAL
DRAWN	TECHNICAL DESIGN - DRAFT
CHECKED	TECHNICAL DESIGN - DRAFT
DATE	08/09/2023

NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION.
2. DO NOT SCALE FROM DRAWINGS.
3. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES.
4. ENSURE COORDINATION WITH OTHER TRADES ON SITE.

PRINCIPAL CONSULTANTS
Architect HAMES SHARLEY
Services NDY
Structural PITCHARD FRANCES
PRINCIPAL CONTRACTOR



[Contractor / Consultant / Document Author]
Hames Sharley
Document Author Project Number



Site	Stage	NEXTDC Project Number
D1	S1	D1.001

Project Address
2 HARVEY STREET,
DARWIN, 0800, NT



Project Name
NEXTDC D1 - LOT 9702

Drawing Title
SECTIONS

Drawing Status
TECHNICAL DESIGN - DRAFT



Drawn	08/09/2023	Sign
Checked	08/09/2023	Seal
Approved	08/09/2023	Seal

Scale	Sheet	File Name	Rev
1 : 100	A1	D1-AR-01-6001	C



																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																									</
--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	----

LEGEND	
	MATERIAL / ITEM - REFER LEGEND
	SELECTED FINISH - REFER SCHEDULES
MATERIAL / ITEM SCHEDULE	
TAG	DESCRIPTION
EX3001	PERFORATED ALUMINIUM SCREENING



30.08.2023	C	TECHNICAL DESIGN - FINAL ISSUE			
30.08.2023	B	TECHNICAL DESIGN - DRAFT ISSUE UPDATE			
21.07.2023	A	TECHNICAL DESIGN - DRAFT ISSUE			
DATE	No.	REVISION HISTORY	DRW	CHK	QA

NOTE:
1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION
2. DO NOT SCALE FROM DRAWINGS
3. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES
4. ENSURE COORDINATION WITH OTHER TRADES ON SITE

PRINCIPAL CONSULTANTS
Architect HAMES SHARLEY
Services NDY
Structural PITCHARD FRANCES
PRINCIPAL CONTRACTOR

CLIENT

NEXTDC
GPO Box 3219
Brisbane QLD 4001
T: +61 7 3177 4777

[Contractor / Consultant / Document Author]
Hames Sharley
Document Author Project Number

Key Plan

Site	Stage	NEXTDC Project Number
D1	S1	D1.001

Project Address
2 HARVEY STREET,
DARWIN, 0800, NT

Project Name
NEXTDC D1 - LOT 9702


Drawing Title
ELEVATIONS - NORTH & EAST

Drawing Status
TECHNICAL DESIGN - DRAFT


DRAWN	DATE	CHKD	DATE
HAS	08/09/2023	HAS	08/09/2023
REVISED	DATE	REVISED	DATE
HAS	08/09/2023	HAS	08/09/2023

Scale	Sheet	File Name
As indicated A1		
Day to		Rev
D1-AR-01-7000		C

LEGEND	
	MATERIAL / ITEM - REFER LEGEND
	SELECTED FINISH - REFER SCHEDULES
MATERIAL / ITEM SCHEDULE	
TAG	DESCRIPTION
CCB001	CFC CLADDING - GREY - TYPE 1
CCB002	CFC CLADDING - GREY - TYPE 2
EXS001	PERFORATED ALUMINIUM SCREENING
GL2001	PAVING GLASS - FRONT POCKET
UN5001	BOUNDARY FENCING - FEATURE
UN5002	BOUNDARY FENCING - SECURITY
RA5004	ROOF ACCESS STEPS & HANDRAIL



1 ELEVATION - SOUTH - GARRAMILA BLVD
1 : 100



2 ELEVATION - WEST - HARVEY ST
1 : 100

05/05/2023	TECHNICAL DESIGN - FINAL				
05/05/2023	TECHNICAL DESIGN - DRAFT				
05/05/2023	WORK IN PROGRESS				
05/05/2023	TECHNICAL DESIGN - DRAFT				
DATE	REV	REVISION HISTORY	DRAWN	CHECKED	DATE
NOTE: 1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH ASSOCIATED SPECIFICATION 2. DO NOT SCALE FROM DRAWINGS 3. CONFIRM ALL MEASUREMENTS ON SITE 4. CHECK ON SITE PRIOR TO CONSTRUCTION AND REPORT ANY DISCREPANCIES 5. ENSURE COORDINATION WITH OTHER TRADES ON SITE					
PRINCIPAL CONSULTANTS					
Architect HAMES SHARLEY					
Services NDY					
Structural PITCHARD FRANCES					
PRINCIPAL CONTRACTOR					
CLIENT					
NEXTDC GPO Box 3219 Brisbane QLD 4001 T: +61 7 3177 4777					
[Contractor / Consultant / Document Author] Hames Sharley					
Document Author Project Number					
Key Plan					
Site	Stage	NEXTDC Project Number			
D1	S1	D1.001			
Project Address					
2 HARVEY STREET, DARWIN, 0800, NT					
Project Name					
NEXTDC D1 - LOT 9702					
Drawing Title					
ELEVATIONS - SOUTH & WEST					
Drawing Status					
TECHNICAL DESIGN - DRAFT					
Drawn	By	05/05/2023			
Checked	By	05/05/2023			
Approved	By	05/05/2023			
Scale	Sheet	File Name			
As indicated A1					
Day to					Rev
D1-AR-01-7001					C

NOTES:

DEMOLITION NOTES


1. COMPLETE FULL CALIBRATION REPORT FOR ALL INSTRUMENTING ROAD SURFACES SURROUNDING THE PROJECT AREA.
2. PROVIDE A SUMMARY OF THE INSTRUMENTATION SYSTEMS, ALL EXTERNAL DEPENDENCIES, AND THE DATA COLLECTION AND ANALYSIS CYCLES TO CLIENT PROJECT MANAGER AND ARCHITECT FOR REVIEW AND APPROVED COMMENTS PRIOR TO ANY WORK.
3. EXTENT TO BE OBSERVED: SHOW IN
3. REFER TO GEOLOGICAL SURVEY FOR SURFACE FEATURES.
4. ALL WORKS SUBJECT TO STRUCTURAL ANALYSIS AND DESIGN BY THE SUB-CONTRACTOR METHOD STATEMENT.
5. THE SUB-CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM SITE BEFORE ANY WORK IS COMMENCED.
6. THE SUB-CONTRACTOR SHALL NOT BE OTHER THAN A REGISTERED PROFESSIONAL ENGINEER REGULATIONS, CODES OF PRACTICE, ETC. SHALL BE APPLIED TO ALL WORKS. HOWEVER, THE VARIATION/DEVIATION TO BE CARRIED OUT.
7. REFER TO RELAYING ENGINEER'S DRAWINGS FOR CAPTAIN'S LEADING OF RESIDENTIAL BUILDING AND THE SUB-CONTRACTOR SHALL BE SEATED ACCORDANCE WITH CHECK ON THE DRAWINGS FOR THE RELEVANT PARTS.
8. CONTRACTORS TO RECORD A PHEON ON EACH SITE PRIOR TO DEMOLITION.
9. FOR INFORMATION ON OR ABOUT EXISTING STRUCTURE, THE SUB-CONTRACTOR SHALL CONSULT THE DRAWINGS.
10. THE SUB-CONTRACTOR SHALL BE RESPONSIBLE FOR THE RELEVANT STRUCTURAL, CIVIL, AND MECHANICAL ENGINEERING CONSULTATION.
11. MAKE SURE THAT THE SUB-CONTRACTOR IS NOT TO EXISTED ADJACENT SURFACES TO BE EXPOSED TO THAT ARE AFFECTED BY THE WORKS.
12. ALL DEMOLITION UNDERSTANDING TO COMPLY WITH THE RELEVANT REGULATIONS.
13. DEMOLITION DRAWINGS TO BE REVIEWED IN CONSULTATION WITH THE ARCHITECTURAL CONSULTANT AND THE SUB-CONTRACTOR SHALL BE SEATED ACCORDANCE WITH CHECK ON THE DRAWINGS FOR THE RELEVANT PARTS.
14. THE SUB-CONTRACTOR SHALL BE RESPONSIBLE FOR THE RELEVANT STRUCTURAL, CIVIL, AND MECHANICAL ENGINEERING CONSULTATION.
15. MAKE SURE THAT THE SUB-CONTRACTOR IS NOT TO EXISTED ADJACENT SURFACES TO BE EXPOSED TO THAT ARE AFFECTED BY THE WORKS.
16. ALL DEMOLITION UNDERSTANDING TO COMPLY WITH THE RELEVANT REGULATIONS.



GENERAL ARRANGEMENT PLANS NOTES

1. CONTRACTOR MUST VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING ANY WORK ON SITE OR PRODUCING SHOP DRAWINGS WHICH MUST BE SUBMITTED FOR REVIEW BEFORE MANUFACTURING.
2. ASSEMBLE ALL WALLS IN ACCORDANCE WITH WALL STIFFENING AND SUPPORT DETAILS ON STRUCTURAL ENGINEER'S DRAWINGS.
3. ALL ENCLOSED APPLICABLE SERVICES OR EQUIPMENT AS SPECIFIED IN NCC D2.7 THAT ARE INSTALLED ALONG PATH OF EGRESS TO INCLUDE SMOKE EXHAUST TO DOORS AND NONV COMBUSTIBLES CONSTRUCTION TO WALLS, CEILINGS AND DOORS AS PER NCC D2.7. REFER DOOR SCHEDULE, DOOR HARDWARE AND SPECIFICATION FOR DETAILS.

LEGEND

WALL HEIGHT
A. FULL UP

- A - FULL HEIGHT TO UNDERSIDE OF STRUCTURE
B - WALL 100mm ABOVE CEILING HEIGHT
C - WALL TO UNDERSIDE OF CEILING
D - REFER TO NOMINATED DETAIL
E - REFER TO ELEVATIONS

KEYNOTE L

- CAR001 ← MATERIAL / ITEM-REFER SCHEDULE
- PNT001 ← SELECTED FINISH-DEFS, SUBMITTALS

MATERIALS

- WATERBURY / FERT SCHEDULE

GETTING NOTES

1. REFER TO SPECIFICATION AND MATERIALS SCHEDULE FOR DETAILS OF CEILING FINISHES AND ASSOCIATED FIXTURES.
2. REFER TO ELECTRICAL, MECHANICAL, FIRE (WET AND DRY, IF APPLICABLE) DOCUMENTATION IN CONJUNCTION WITH THIS DRAWING TO COORDINATE CEILING MOUNTED SERVICES. REFER TO ARCHITECT ANY DISCREPANCIES OR CLASHES BETWEEN SERVICES TO BE INSTALLED.
3. REFER TO INSULATION DIAGRAMS & SPECIFICATION FOR TOTAL INSULATION EXTENT. TO BE REVIEWED IN CONJUNCTION WITH SECTION J REPORT

ELEVATION NOTES

1. ROOF ACCESS AND FALL ARREST SYSTEMS SHOWN ON DRAWINGS ARE FOR DESIGN INTENT ONLY. FINAL SYSTEM TO BE DESIGNED AND SUPPLIED BY ACCESS SAFETY CONSULTANT.

DOORS NOTES


- [illegible]

WALL SCHEDULE NOTES


5. STUO SPACING FOR ACoustically RATED WALLS TO NOT BE REDUCED FROM 800mm OF UNLESS NOTED OTHERWISE.
6. MINIMUM STUO GAUGES FOR ACoustically RATED WALLS TO BE 12.5 BUT UNLESS NOTED OTHERWISE.
7. PARTITION TO BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS' INSTRUCTIONS UNLESS NOTED OTHERWISE.
8. MAKE ALLOWANCE FOR ADDITIONAL NOISEBARS AND PLYWOOD/STEEL SHEET LINING TO BE APPLIED TO EXISTING WALL TO ACHIEVE DESIGN PLASTERED SURFACE WITH FINISH STRUCTURE AND FORM FOR THE INSTALLATION OF AN EQUIPMENT. REFER TO THE DRAWING FOR DIMENSIONS AND LOCATIONS.
9. REFER TO SECURITY CONSULTANT DRAWINGS FOR FURTHER SPECIFIC DETAILS & REQUIREMENTS FOR PHYSICAL SECURITY OF THE SHEET LINING TO BE APPLIED TO PLYWOOD/STEEL SHEET LINING TO BE APPLIED TO EXISTING WALL TO ACHIEVE DESIGN PLASTERED SURFACE WITH FINISH STRUCTURE AND FORM FOR THE INSTALLATION OF AN EQUIPMENT. REFER TO THE DRAWING FOR DIMENSIONS AND LOCATIONS OR CONFIRM WITH SECURITY CONSULTANT WHEN MULTIPLE SECURE ROOMS ADJACENT.
10. STEEL STUDWORK BEYOND CALCULATIONS AS NOTED TO BE REDUCED TO 400mm UNLESS OTHERWISE NOTED IN THE WALL SCHEDULE BELOW WHERE STIPULATED TO BE REDUCED TO 400mm UNLESS OTHERWISE NOTED.

LEGENDS:


FRE SEPARATION LEGEND



INSULATION LEGEND




ACUSTIC LEGEND



NOTE: REFER TO FACADE ENGINEER'S DOCUMENTATION FOR EXTERNAL GLAZING U VALUES.

WATERPROOFING LEGEND




NOTE:
WATERPROOFING SYSTEMS HAVE BEEN
NOMINALLY INDICATED. FINAL SPECIFICATIONS &
SYSTEMS TO BE CONFIRMED WITH SUPPLIER &
CONTRACTOR ONCE THE FRONT-OF-HOUSE
CONSTRUCTION METHODOLOGY HAS BEEN
AGREED.


NOTE:
WATERPROOFING TO WET AREAS TO BE
INSTALLED IN ACCORDANCE TO AS 3740.
SHOWERS & WASH DOWN AREA WALLS TO HAVE
WATERPROOFING TO MIN. 1800MM ABOVE FFL.

NOTE:
ALL HOBS AND BUNDS TO BE WATERPROOFED.


FOUNDATION SETOUT LEGEND




CONCRETE PROFILE LEGEND




CONCRETE PROFILE - PLINTH & COLUMN SETOUT



CEILING LEGEND



																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					</
--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	----



PRELIMINARY PLANT SCHEDULE

TREES						
CODE	SPECIES NAME	COMMON NAME	SPACINGS (mm)	POT SIZE (L)	QUANTITY	SIZE AT MATURITY (HXW)
FT01	Syzgium armstrongii	Small White Bush Apple	as shown	60L	20	6-8 x 1.5m
FT02	Hibiscus tiliaceus rubra	Cottonwood Hibiscus	as shown	28L air-prune pot	5	4-7 x 3-5m*

Sizes under cultivation typically reduced. Species suitable for maintenance pruning to smaller form.*

GB01 - Low Frontage Plantings						
CODE	SPECIES NAME	COMMON NAME	SPACINGS (mm)	% of cover	POT SIZE (L)	QUANTITY
MWA'	Melaleuca 'White Anzac'	White Anzac	600	30%	40mm / megatube	32
Mc	Molineria capitulata	Palm Grass	600	20%	40mm / megatube	21
Gp	Goodenia psidioides	Glennie River	400	30%	40mm / megatube	71
Vr	Vitex rotundifolia	Beach vitex	400	20%	40mm / megatube	48


GB02 - Garden Bed						
CODE	SPECIES NAME	COMMON NAME	SPACINGS (mm)	POT SIZE (L)	QUANTITY	SIZE AT MATURITY (HXW)
HL	Hymenocallis littoralis	Spider Lily	400mm	40mm / megatube	69	0.5 x 0.5m
Lr	Leea rubra		as shown	40mm / megatube	10	1-2 x 2m

GB03 - Lower Garden Plantings						
CODE	SPECIES NAME	COMMON NAME	SPACINGS (mm)	% of infill cover	POT SIZE (L)	QUANTITY
Gp	Gardenia psidioides	Glennie River	500	40%	40mm / megatube	27
Sp	Stenochlaena palustris	Climbing Swamp Fern	500	20%	40mm / megatube	11
As	Sansevieria trifasciata	Snake Plant	500	20%	40mm / megatube	11
Tp	Triodia pungens	Soft Spinifex	500	20%	40mm / megatube	11

GB04 - Entry Plantings						
CODE	SPECIES NAME	COMMON NAME	SPACINGS (mm)	% of cover	POT SIZE (L)	QUANTITY
Lr	Grevillea dyandri	Dyandri	as shown		140mm / megatube	14
Gd	Leea rubra	Leea rubra	as shown		140mm / megatube	13
MWA'	Melaleuca 'White Anzac'	White Anzac	600	30%	40mm / megatube	36
Gf	Grevillea formosa	Mt Brockman	600	30%	40mm / megatube	36
Mc	Molineria capitulata	Palm Grass	600	20%	40mm / megatube	24
Gp	Goodenia psidioides	Glennie River	600	20%	40mm / megatube	24

GB05 - Swale Plantings						
CODE	SPECIES NAME	COMMON NAME	SPACINGS (mm)	% of infill cover	POT SIZE (L)	QUANTITY
Lr	Lomandra fluviatilis 'Shara / ABLU'	Mat Rush	300	100%		95

SL01 - Lawn/Turf						
CODE	SPECIES NAME	COMMON NAME	SPACINGS (mm)	% of infill cover	POT SIZE (L)	QUANTITY
Zsp.	Zoysia sp.	Sir Grange Zoysia	400	100%	turf	31.9m ²



LEGEND

- Extent of Works
- Syzgium armstrongii (FT01)
Refer detail 05/L007
- Hibiscus tiliaceus rubra (FT02)
Refer detail 05/L007
- Varies - refer annotation.
Refer detail 04/L007
- Garden Bed - Type GB1
Low Planting, Refer detail 02/L007
- Garden Bed - Type GB2
Tall Planting, Refer detail 01/L007
- Garden Bed - Type GB3
Tree + Low Planting, Refer detail 02/L007
- Garden Bed - Type GB4
Tree + Tall Planting, Refer detail 02/L007
- Garden Bed - Type GB5
Planted Swale Species TBC.
- Lawn/Turf - SL01
Zoysia Turf, Refer detail 03/L007

- PLANTING NOTE:
- PLANT SPECIES IN GROUPINGS OF 3-6 OF SAME SPECIES, UNLESS OTHERWISE INDICATED.
 - PLANTINGS TO BE OFFSET MIN. 400MM FROM GARDEN BED EDGE.
 - REFER L007 FOR SOFTSCAPE PLANTING DETAILS.
 - PREFERRED SUPPLIER:

TERRITORY NATIVE PLANTS

Contact: Tim Moore
Info@territorynativeplants.com.au
0429 095 733

W: territorynativeplants.com.au
F: TNP Facebook

NOTE:
REFER L008 FOR TYPICAL SOFTSCAPE PLANTING DETAILS.

ANY DISCREPANCIES BETWEEN SUB-CONSULTANTS DRAWINGS TO BE RAISED WITH SUPERINTENDENT, FOR CLARIFICATION.

ALL LANDSCAPE DRAWINGS TO BE READ IN CONJUNCTION WITH ENGINEERS PLANS, DETAILS AND SPECIFICATION.

SURVEY SERVICES SHOWN IN BLUE FOR COORDINATION PURPOSES.



Rev	Date	Revision Details	By	Chk	App
P3	28.09.23	40% DOCUMENTATION ISSUE	TZ	GL	DS
P2	07.06.23	40% DOCUMENTATION ISSUE	DH	GL	DS
P1	26.05.23	PRELIMINARY 40% ISSUE	DH	GL	DS

NEXT DC D1 LANDSCAPE WORKS

8 RYKO COURT, DARWIN, NT 0800

T.C.L.
TERRITORY CONSULTANTS

Designed by
Status:
TZ
40% DOCUMENTATION
FOR DESIGN & CONSTRUCT

Drawing: PLANTING PLAN	Date: 08.09.2023	Rev: P3
Sheet: 01 of 01	Scale: 1:50 @ A1	
Purpose: LANDSCAPE ARCHITECTURE	Drawing No. L004	


Drawing number 2023/0228/16

Referred to in Permit No: DP23/0213


FINISH TOLERANCES

Thickness	Surface Level	Level
Maximum Deviation	Maximum Deviation	Discontinuity
± 5mm	± 3mm of specified level	2mm


Integrity Insitu Colour Concrete (32MPa)
Colour: TBC
Finish: Lightly Exposed Aggregate
Structure: Refer Engineer's documentation




01 PV01 - CONCRETE PAVEMENT
Typical Detail Scale 1:10




02 PV03 RUBBLE - NON-TRAFFICABLE
Typical Detail Scale 1:10




03 ED01 STEEL EDGE
Typical Detail Scale 1:10



04 ED03 STEEL EDGE
Typical Detail Scale 1:10



05 ED02 / GB03 GARDEN BED PLANTING
Typical Detail Scale 1:20



06 ED04 - CONCRETE KERB (INDICATIVE ONLY)
Typical Detail Scale 1:10

NOTES:

- All drawings and documentation to be read in conjunction with L000 Drawing notes, Architectural & Engineers documentation.
- Details provided are typical, and indicative only, to be developed through Design & Construct contract.
- All setbacks to be marked up by Contractor & approved by Landscape Architect prior to construction.
- Contractor to notify the Superintendent of any discrepancies between Landscape Architects & Engineer's drawings & existing site conditions prior to any works, all drawings shall be read in conjunction with the specification.
- All levels and dimensions must be verified on site before commencing construction, fabrication or shop drawings.
- Principals authorised representative to check set out prior to construction commencing.
- Levels to match or build up on existing, minor excavation may be required in some locations to allow for DDA compliance and clearance of structures.
- Site equipment to be appropriately sized and commensurate to scale of works, to minimise overall disturbance to site
- Cross falls and grading by Engineer's, Refer Engineer's documentation.
- All signage & wayfinding by others.



NEXT DC D1 LANDSCAPE WORKS

8 RYKO COURT, DARWIN, NT 0800

File #: D2302

Rev	Date	Revision Details	By	CHK	App
P3	08.09.23	40% DOCUMENTATION ISSUE	TZ	GL	DS
P2	07.06.23	40% DOCUMENTATION ISSUE	DH	GL	DS
P1	26.05.23	PRELIMINARY 40% ISSUE	DH	GL	DS

T.C.L
T.A.L. 08.08.2017

Designed by TCL	Drawn by TZ	Checked by GL	Approved by DS	Drawing: TYPICAL HARDSCAPE DETAILS	Date: 08.09.2023
Status: 01 of 03	40% DOCUMENTATION FOR DESIGN & CONSTRUCT			Sheet: 01 of 03	Scale: As shown @ A1
Purpose: LANDSCAPE ARCHITECTURE				Drawing No. L005	Rev. P3



~~Tactile Paver (FX03) in cast in-situ coloured concrete stair. Refer detail 06 & specification~~

Latham Strip non-slip stair nosing (FX02). Refer detail 11 & specification


Stair Riser Height Based On
Grading Refer
Engineer' Documentation

SS316 Tubular steel handrail in 50,8mm Ø CHS, Angle grind all external welds to achieve a clean junction between adjoining metal work. Contractor to provide shop drawings with setout and finishes for approval prior to fabrication. To comply with AS 1428.1,

Tactile Paver (FX03) in cast in-situ coloured concrete stair. Refer detail 06 & specification


01 | CAST IN SITU CONCRETE STAIR

Scale 1:10



02 | CAST IN SITU CONCRETE STAIR

Scale 1:10



03 STEP NOSING

Scale 1:5

NOTES:

1. All drawings and documentation to be read in conjunction with L000 Drawing notes, Architectural & Engineers documentation.
2. Details provided are typical, and indicative only, to be developed through Design & Construct contract.
3. All setouts to be marked up by Contractor & approved by Landscape Architect prior to construction.
4. Contractor to notify the Superintendent of any discrepancies between Landscape Architects & Engineer's drawings & existing site conditions prior to any works, all drawings shall be read in conjunction with the specification.
5. All levels and dimensions must be verified on site before commencing construction, fabrication or shop drawings.
6. Principals authorised representative to check set out prior to construction commencing.
7. Levels to match or build up on existing, minor excavation may be required in some locations to allow for DDA compliance and clearance of structures.
8. Site equipment to be appropriately sized and commensurate to scale of works, to minimise overall disturbance to site
9. Cross falls and grading by Engineer's, Refer Engineer's documentation.
10. All signage & wayfinding by others.



P2	08/09/23	40% DOCUMENTATION ISSUE	TZ	GL	DS							
P1	07/06/23	40% DOCUMENTATION ISSUE	DH	GL	DS							
Rev	Date	Revision Details	Bv	Chk	Appr							

NEXT DC D1 LANDSCAPE WORKS


8 RYKO COURT, DARWIN, NT 0800

File #: D2302


02	Designed by TCL	Drawn by TZ	Checked by GL	Approved by DS	Drawing: TYPICAL HARDSCAPE SETOUT DETAILS Sheet: 02 of 03	Date: 08.09.2023 Scale: As shown @ A1	
Status: 40% DOCUMENTATION FOR DESIGN & CONSTRUCT					Purpose: LANDSCAPE ARCHITECTURE	Drawing No. L006	Rev. P2

Drawing number 2023/0228/18


Referred to in Permit No: DP23/0213




01 GB02/GB04 RAISED GARDEN BED
Typical Detail Scale 1:10




02 GB01/GB03 GARDEN BED
Typical Detail Scale 1:10



03 SL01 - ROLL OUT TURF
Typical Detail Scale 1:10



04 GARDEN BED PLANTING
Typical Detail Scale 1:10



05 SEMI-ADVANCED TREE PLANTING
Typical Detail Scale 1:20

NOTES:

- All drawings and documentation to be read in conjunction with L000 Drawing notes, Architectural & Engineers documentation.
- Details provided are typical, and indicative only, to be developed through Design & Construct contract.
- All setbacks to be marked up by Contractor & approved by Landscape Architect prior to construction.
- Contractor to notify the Superintendent of any discrepancies between Landscape Architects & Engineer's drawings & existing site conditions prior to any works, all drawings shall be read in conjunction with the specification.
- All levels and dimensions must be verified on site before commencing construction, fabrication or shop drawings.
- Principals authorised representative to check set out prior to construction commencing.
- Levels to match or build up on existing, minor excavation may be required in some locations to allow for DDA compliance and clearance of structures.
- Site equipment to be appropriately sized and commensurate to scale of works, to minimise overall disturbance to site
- Cross falls and grading by Engineer's. Refer Engineer's documentation.
- All signage & wayfinding by others.



NEXT DC D1 LANDSCAPE WORKS

8 RYKO COURT, DARWIN, NT 0800

File #: D2302

Rev	Date	Revision Details	By	Chk	App
P3	08.09.23	40% DOCUMENTATION ISSUE	TZ	GL	DS
P2	07.06.23	40% DOCUMENTATION ISSUE	DH	GL	DS
P1	26.05.23	PRELIMINARY 40% ISSUE	DH	GL	DS

T.C.L
T.A.L. O.E. C.U. L.T.Y. L.T.C. L.T.E. L.N.

Designed by TCL	Drawn by TZ	Checked by GL	Approved by DS	Drawing: TYPICAL SOFTSCAPE DETAILS	Date: 08.09.2023
Status: 40% DOCUMENTATION	Sheet: 03 of 03	Purpose: LANDSCAPE ARCHITECTURE	Drawing No: L007	Scale: As shown @ A1	Rev: P3

PRELIMINARY LANDSCAPE SURFACES, FURNITURE & FIXTURES TYPE SCHEDULE

This schedule is to be referred to when reading the TCL documentation drawings.

Detail Types directly reference the drawing details.

Contractor to advise any discrepancies between information provided in this Schedule with Referenced details, prior to ordering of materials.

Detail Type	Description	Location	Detail Reference No.	Size / Profile	Finish / Colour	Notes	Supplier - TCL Comment
SURFACES							
PV01	Integrally Coloured Concrete	DDA / Main pedestrian access areas - Refer Surfaces Plan L003	01/L005	120mm slab, with thickened edge profile. Refer Engineer's documentation	Lightly Exposed Aggregate - finish to achieve P5 non-slip surface rating. To be integrally coloured to match external architectural external finishes. Colour to be confirmed by Landscape Architect subject to confirmation of above	Specification to satisfy P5 Slip Resistance rating for new pedestrian pavements - AS 4586:2013, 3 x 300x300mm sample panels to be	Supplier: Boral Darwin Contact: 08 8947 3480 https://www.boral.com.au/products/concrete/dec-tive-concrete/coloured-concrete
PV02	Asphalt Pavement	Driveway & DDA Parks - Refer Surfaces Plan L003	Refer Engineer's	N/A	Refer Engineer's	Refer Engineer's Documentation	Supplier: NT Bitumen Contact: 08 8963 3298 http://www.ntbitumen.com.au/
PV03	Inorganic Gravel Pavement	Lower Garden (crushed gravel surrounds to pavement bands) - Refer Surfaces Plan L003	02/L005	PM2/20	Quartzite Quarry Rubble	Sample for Approval by Landscape Architect	Supplier: Rural Garden Supplies (Humpty Doo) Contact: 08 8988 5880 https://www.ruralgardensupplieshumptydoo.com/
ED01	Steel Edge - Raised 150mm Formboss Redcor	Lower Garden / GB01 Interface - Refer Surfaces Plan L003	04/L005	290mm H x 2.5mm W typical Profile - installed (up to) 400mm above FSL	'Redcor' Rusted Finish	Install to manufacturers specifications	Alternate Supplier: Top End Steel Supplies Contact: (0498) 656 888 https://topendsteelsupplies.com.au/
ED02	Steel Edge - Raised 400mm Formboss Redcor	Lower Garden / GB01 Interface - Refer Surfaces Plan L003	06/L005	580mm H x 2.5mm W typical Profile - installed (up to) 400mm above FSL	'Redcor' Rusted Finish	Install to manufacturers specifications	
ED03	Steel Edge - Flush Formboss Redcor	Lower Garden Bed (GB03) & Lawn / Garden Bed (SL01 / GB02) Interface - Refer Surfaces Plan L003	04/L005	100mm H x 2.5mm W typical Profile - installed flush	'Redcor' Rusted Finish	Install to manufacturers specifications	
ED04	Concrete Kerb Edging / Watertable - Cast in-situ	Kerb Edge - Refer Surfaces Plan L003	Refer Engineer's	110mm H x 230 (watertable) / 80mm (kerb) W (typical)	Colour to match PV01. Finish TBC	Refer Engineer's	Supplier: APJ Concrete Contact: 08 8953 1939 https://www.apjconcrete.com.au/
ED05	Trench Grate ACO KlassDrain K200 series	Refer Surfaces Plan L003	Manufacturers specification	To be nominated by Civil Engineer's, for approval by Landscape Architect	SS Heelsafe® Anti-Slip grate	Install to manufacturers specifications	Supplier: Contractor to nominate for approval by Landscape Architect https://www.acodrain.com.au/products/klaskdrain/
MU01	Organic Mulch	ALL Garden Beds	N/A	75mm D	Forest Mulch	Specification to satisfy AS4419.	Supplier: Rural Garden Supplies (Humpty Doo) Contact: 08 8988 5880 https://www.ruralgardensupplieshumptydoo.com/

Detail Type	Description	Location	Detail Reference No.	Size	Finish	Notes	Notes
FIXTURES							
FX01	Wheelstop Replas	Carpark	NA	100mm H x 1650mm L x 150mm W	Precast concrete	Install to comply AS/NZS 2890.1:2004. Sample, Prototype Layout, Testing Data for Approval by Landscape Architect	Supplier: Contractor to nominate for approval by Landscape Architect Contact:
FX02	Tactile nosing Strip Latham Australia ACS-50SK Cast-In Place Tread	Terrace Steps	NA	10mm H x L (to match steps) x 50mm W	Luminance contrast in a range of 30% to 60% is achieved, based on the final PV01 Concrete Pavement selection.	Install to comply AS/NZ 1428.1:2009 Design for access and mobility, and in accordance with manufacturers specifications.	Supplier: Contractor to nominate for approval by Landscape Architect Contact:
FX03	Tactile pavers Urbanstone Engineered Tactile paver	Terrace Steps and Kerb Ramp	N/A	40mm H x 300mm L x 300mm W			Supplier: Contractor to nominate for approval by Landscape Architect Contact:
Tree Planting	Tree Stakes Hardwood	Garden Beds	05/L007	1800mm H x 50mm L x 50mm W & hessian ties	Sawn	Stakes to be straight, and free of major creaking and splits	Supplier: Rural Garden Supplies (Humpty Do) Contact: 08 9989 5860 https://www.ruralgardensupplieshumptydo.com/
Detail Type	Description	Location	Detail Reference No.	Size	Finish	Notes	Notes
FURNITURE							
FN01	Bench Seat Bottom & Gardiner Avenue Plinth Bench mounted to Concrete (PV01) Plinth	<u>Upper Terrace Lawn</u> (Proprietary) & <u>Lower Garden</u> (Modified Proprietary). Refer Surfaces Plan	N/A	<u>Upper Terrace</u> 1800mm L x 380mm D x 450mm H (finished height). <u>Lower Garden</u> Trim length to match concrete profiles documented. 380mm D x 450mm H (finished height). <u>General</u> Install bench to 50mm overhanging to front face of plinth	Oiled Blackbutt battens with Zinc primed powder-coated frame in Black Satin. Concrete colour & finish to match PV01 Concrete Pavements, profile to match documentation. Side faces to Class 2 Off-Form finish	Shop drawings for Approval by Landscape Architect prior to manufacture. Seat to be mounted to top of concrete plinth.	Supplier: Bottom & Gardiner Sydney Contact: https://www.bottomgardiner.com.au/products/urban-and-street-furniture/urban-benches/avenue-plinth-bench/

SOIL SCHEDULE

This schedule is to be referred to when reading the TCL documentation drawings.

Detail Types directly reference the drawing details.

Contractor to advise any discrepancies between information provided in this Schedule with Referenced details, prior to ordering of materials.

Detail Type	Description	Location	Detail Reference No.	Size / Profile	Notes	Supplier - TCL Comment
TYPE A	Imported Top Soil - Type A	Garden Beds (GB01-GB04)	N/A	Garden Blend - Premium Super Soil Mix.	Specification to satisfy AS4419, and Soil Type as specified below	Supplier: Rural Garden Supplies (Humpty Doo) Contact: 08 8988 5880 https://www.ruralgardensupplieshumptydoo.com/
TYPE B	Imported Top Soil - Type B	Garden Beds (GB01-GB04) & Turf Lawn (SL01)	N/A	Type A Top Soil (Proprietary name) Screened sandy loam top soil	Specification to satisfy AS4419.	Supplier: Rural Garden Supplies (Humpty Doo) Contact: 08 8988 5880 https://www.ruralgardensupplieshumptydoo.com/
Soil Type	pH	Salt Content	Additives	Drainage rate	Fertiliser	Notes
Imported Top Soil	pH (water) 5.5-7.5 (unless otherwise specified)	(EC) 5 soil water <0.6 dS/m (or equivalent measure of total dissolved salts [TDS])	(non-fertilizer) by volume 20% composted organic matter by volume (To AS4544 - 2003)	as measured by saturated hydraulic conductivity, after additives incorporation; Not less than 60mm/hr and no greater than 120mm/hr. Test as per AS4419-2003	Super Phosphate 250 g/m³ Incitec Phos PastureBoosta (or similar) 600 g/m³	Micromax Trace Element Mix 300 g/m³ Magnesium sulphate 400 g/m³ Slow release fertilizer 10-14 month release rate 80 g/s/m after planting Sample, Testing Data for Approval by Landscape Architect

[illegible]

ERROR: undefined
OFFENDING COMMAND: eexec

STACK:

/quit
-dictionary-
-mark-

ERROR: undefined
OFFENDING COMMAND: eexec

STACK:

/quit
-dictionary-
-mark-